



OFFICE OF THE PURCHASING AGENT

TOWN OF ARLINGTON  
730 Massachusetts Avenue  
Arlington, MA 02476

Telephone (781) 316-3003  
Fax (781) 316-3019

DATE: April 8, 2013

TO ALL BIDDERS

BID NO. 13-04

SUBJECT: 6<sup>th</sup> Floor Office Renovation/ Arlington High School

**ADDENDUM NO. 2**

TO WHOM IT MAY CONCERN:

With reference to the bid request relative to the above subject, please note the following:


**SEE ATTACHED**

**BIDDER MUST ACKNOWLEDGE ADDENDUM WITH SUBMISSION**

All other terms, conditions and specifications remain unchanged.

Very truly yours,

Town of Arlington

  
Domenic R. Lanzillotti  
Purchasing Officer



DATE: April 8, 2013

**ADDENDUM NO. 2**

6<sup>TH</sup> FLOOR OFFICE RENOVATION  
ARLINGTON HIGH SCHOOL

This addendum becomes an integral part of the bid documents and must be acknowledged on the bid form.

**SUBMITTED BID QUESTIONS:**

**Question 1:**

Will the mechanical contractor be responsible for providing all the VFD's?

**Answer 1:**

Mechanical contractor is to provide the VFD's for the new rooftop unit RTU-1 only. Electrical contractor (E.C.) to provide VFD's for the existing RTU as referenced in note #11 under "Mechanical Schedule Notes" and listed on the "Mechanical Schedule" on drawing E3.1.

**Question 2:**

Who is the Fire Alarm testing company?

**Answer 2:**

Fire Alarm Company is Commercial Fire.

**Question 3:**

Manufacturer for existing panels boards PA & DA. And any other information on existing panels boards to help get accurate cost on breakers?

**Answer 3:**

Existing Panel "PA" and "DA" are ITE panels.

**Question 4:**

All spaces are open ceiling-must be in conduit? Besides the one area shown with ACT.

**Answer 4:**

All new wiring shall be concealed where possible. Utilize existing attic space above for all wiring and conceal in walls. Wiremold raceway system shall be used where wiring is exposed and cannot be concealed.