


# TOWN OF ARLINGTON

# BID #16-19 WATER DISTRIBUTION SYSTEM IMPROVEMENTS APRIL 20, 2016

# PLAN LIST:

JASON STREET AREA - SHEETS 2-6
TYPICAL CONSTRUCTION DETAILS: SHEET 7




- 1. This plan was developed using available aerial imagery, existing plans & on—site observations.
- 2. An on—the—ground survey was not conducted during the development of this plan. The location and dimensions of features shown on this plan are approximate. It shall be the sole responsibility of the contractor to determine locations of any existing utilities and/or features not shown on this plan
- 3. The contractor shall notify the Town of Arlington Engineering Division and/or Water/Sewer Division of all discrepancies from this plan identified in the field.
- 4. All on—site drainage catch basins shall be equipped with an inlet protection device during all construction activities. Any sediment that enters the Town's Stormwater Sewer System as a result of this work shall be removed by the contractor at his cost.
- 5. Any areas disturbed by the contractor outside the limits of work shall be restored to original condition at no cost to the owner.
- 6. The contractor must notify all utilities prior to performing any excavation work. The Town of Arlington is not a member of "Dig—Safe" and must be notified directly at least 72—Hours prior to any excavation at 781—316—3310 or 781—316—3301.
- 7. The location, number, & type of proposed fittings shown on this plan are intended for illustrative purposes only. Field conditions will dictate the location, number, & type of fittings required. All installations shall be to the full satisfaction of the Town of Arlington.
- 8. The location of proposed water service laterals are not shown on this plan. The location of new 34" copper service laterals shall be field determined and laid out to the satisfaction/approval of the Town of Arlington.
- 9. Trenches shall be backfilled with suitable material and compacted in layers not over 6" deep using mechanical compactors or jet—rodding. Backfill material shall be compacted to 95% of maximum dry density as determined by AASHTO Standard Test T99 Method C.

No. Revision/Issue Date



# Water Distribution System Improvements Plan

Project: JAS-0001	Sheet
Drawn By: KPK	7 <b>7</b>
Scale: 1" = 20'	$\neg$ $\angle$ 0I /
Date: 4/11/2016	



- 1. This plan was developed using available aerial imagery, existing plans & on—site observations.
- 2. An on—the—ground survey was not conducted during the development of this plan. The location and dimensions of features shown on this plan are approximate. It shall be the sole responsibility of the contractor to determine locations of any existing utilities and/or features not shown on this plan
- 3. The contractor shall notify the Town of Arlington Engineering Division and/or Water/Sewer Division of all discrepancies from this plan identified in the field.
- 4. All on—site drainage catch basins shall be equipped with an inlet protection device during all construction activities.

  Any sediment that enters the Town's Stormwater Sewer System as a result of this work shall be removed by the contractor at his cost.
- 5. Any areas disturbed by the contractor outside the limits of work shall be restored to original condition at no cost to the owner.
- 6. The contractor must notify all utilities prior to performing any excavation work. The Town of Arlington is not a member of "Dig—Safe" and must be notified directly at least 72—Hours prior to any excavation at 781—316—3310 or 781—316—3301.
- 7. The location, number, & type of proposed fittings shown on this plan are intended for illustrative purposes only. Field conditions will dictate the location, number, & type of fittings required. All installations shall be to the full satisfaction of the Town of Arlington.
- 8. The location of proposed water service laterals are not shown on this plan. The location of new 3/4" copper service laterals shall be field determined and laid out to the satisfaction/approval of the Town of Arlington.
- 9. Trenches shall be backfilled with suitable material and compacted in layers not over 6" deep using mechanical compactors or jet—rodding. Backfill material shall be compacted to 95% of maximum dry density as determined by AASHTO Standard Test T99 Method C.


No. Revision/Issue Date

Prepared By:



# Water Distribution System Improvements Plan

Project: JAS-0001	Sheet
Drawn By: KPK	7 7
Scale: 1" = 20'	
Date: 4/11/2016	



- 1. This plan was developed using available aerial imagery, existing plans & on—site observations.
- 2. An on—the—ground survey was not conducted during the development of this plan. The location and dimensions of features shown on this plan are approximate. It shall be the sole responsibility of the contractor to determine locations of any existing utilities and/or features not shown on this plan.
- 3. The contractor shall notify the Town of Arlington Engineering Division and/or Water/Sewer Division of all discrepancies from this plan identified in the field.
- 4. All on—site drainage catch basins shall be equipped with an inlet protection device during all construction activities.


  Any sediment that enters the Town's Stormwater Sewer System as a result of this work shall be removed by the contractor at his cost.
- 5. Any areas disturbed by the contractor outside the limits of work shall be restored to original condition at no cost to the owner.
- 6. The contractor must notify all utilities prior to performing any excavation work. The Town of Arlington is not a member of "Dig—Safe" and must be notified directly at least 72—Hours prior to any excavation at 781—316—3310 or 781—316—3301.
- 7. The location, number, & type of proposed fittings shown on this plan are intended for illustrative purposes only. Field conditions will dictate the location, number, & type of fittings required. All installations shall be to the full satisfaction of the Town of Arlington.
- 8. The location of proposed water service laterals are not shown on this plan. The location of new 3/4" copper service laterals shall be field determined and laid out to the satisfaction/approval of the Town of Arlington.
- 9. Trenches shall be backfilled with suitable material and compacted in layers not over 6" deep using mechanical compactors or jet—rodding. Backfill material shall be compacted to 95% of maximum dry density as determined by AASHTO Standard Test T99 Method C.

No. Revision/Issue Date



## Water Distribution System Improvements Plan

Project: JAS-0001	Sheet
Drawn By: KPK	7 of -
Scale: 1" = 20'	7 <b>4</b> 01 /
Date: 4/11/2016	_ •




- 1. This plan was developed using available aerial imagery, existing plans & on—site observations.
- 2. An on—the—ground survey was not conducted during the development of this plan. The location and dimensions of features shown on this plan are approximate. It shall be the sole responsibility of the contractor to determine locations of any existing utilities and/or features not shown on this plan.
- 3. The contractor shall notify the Town of Arlington Engineering Division and/or Water/Sewer Division of all discrepancies from this plan identified in the field.
- 4. All on—site drainage catch basins shall be equipped with an inlet protection device during all construction activities. Any sediment that enters the Town's Stormwater Sewer System as a result of this work shall be removed by the contractor at his cost.
- 5. Any areas disturbed by the contractor outside the limits of work shall be restored to original condition at no cost to the owner.
- 6. The contractor must notify all utilities prior to performing any excavation work. The Town of Arlington is not a member of "Dig-Safe" and must be notified directly at least 72-Hours prior to any excavation at 781-316-3310 or 781-316-3301.
- 7. The location, number, & type of proposed fittings shown on this plan are intended for illustrative purposes only. Field conditions will dictate the location, number, & type of fittings required. All installations shall be to the full satisfaction of the Town of Arlington.
- 8. The location of proposed water service laterals are not shown on this plan. The location of new 34" copper service laterals shall be field determined and laid out to the satisfaction/approval of the Town of Arlington.
- 9. Trenches shall be backfilled with suitable material and compacted in layers not over 6" deep using mechanical compactors or jet—rodding. Backfill material shall be compacted to 95% of maximum dry density as determined by AASHTO Standard Test T99 Method C.


No. Revision/Issue Date





# Water Distribution System Improvements Plan


Project: JAS-0001	Sheet
Drawn By: KPK	7
Scale: 1" = 20'	$\neg$ OI /
Date: 4/11/2016	



























- 1. This plan was developed using available aerial imagery, existing plans & on—site observations.
- 2. An on-the-ground survey was not conducted during the development of this plan. The location and dimensions of features shown on this plan are approximate. It shall be the sole responsibility of the contractor to determine locations of any existing utilities and/or features not shown on this plan.
- 3. The contractor shall notify the Town of Arlington Engineering Division and/or Water/Sewer Division of all discrepancies from this plan identified in the field.
- 4. All on—site drainage catch basins shall be equipped with an inlet protection device during all construction activities. Any sediment that enters the Town's Stormwater Sewer System as a result of this work shall be removed by the contractor at his cost.
- 5. Any areas disturbed by the contractor outside the limits of work shall be restored to original condition at no cost to the owner.
- 6. The contractor must notify all utilities prior to performing any excavation work. The Town of Arlington is not a member of "Dig—Safe" and must be notified directly at least 72—Hours prior to any excavation at 781—316—3310 or 781—316—3301.
- 7. The location, number, & type of proposed fittings shown on this plan are intended for illustrative purposes only. Field conditions will dictate the location, number, & type of fittings required. All installations shall be to the full satisfaction of the Town of Arlington.
- 8. The location of proposed water service laterals are not shown on this plan. The location of new 3/4" copper service laterals shall be field determined and laid out to the satisfaction/approval of the Town of Arlington.
- 9. Trenches shall be backfilled with suitable material and compacted in layers not over 6" deep using mechanical compactors or jet—rodding. Backfill material shall be compacted to 95% of maximum dry density as determined by AASHTO Standard Test T99 Method C.





### Water Distribution System Improvements Plan

Project: JAS-0001	Sheet
Drawn By: KPK	$ extstyle  ag{7}$
Scale: 1" = 20'	$\neg$ / OI /
Date: 4/11/2016	