Site Plans

Issued for Local Approvals February 9, 2022 Date Issued April 21, 2022 Latest Issue

Proposed Self Storage Facility

34 Dudley Street Arlington, Massachusetts

Owner

34 Dudley Street LLC 34 Dudley Street Arlington, MA 02476

Applicant

PSI Atlantic Arlington MA, LLC 530 Oak Court Drive Suite 155 Memphis, TN 38117

Assessor's Map: 55 Lot: 2-39.B



Sheet Index				
No.	Drawing Title	Latest Issue		
C1.01	Legend and General Notes	4/21/2022		
C2.01	Site Preparation Plan	4/21/2022		
C3.01	Layout and Materials Plan	4/21/2022		
C4.01	Grading, Drainage, and Erosion Control Plan	4/21/2022		
C5.01	Utility Plan	4/21/2022		
C6.01-C6	.03 Site Details	4/21/2022		
L1.01	Planting Plan	4/21/2022		
L2.01	Planting Details	2/9/2022		

Reference I	Reference Drawings				
No.	Drawing Title	Latest Issue			
Sv-1	Existing Conditions Plan of Land	11/5/2021			
SL-1	Site Lighting Plan	4/21/2022			
A-101 to A-106	Floor Plans	4/12/2022			
A-201 to A-202	Exterior Elevations	4/12/2022			



Michael Parker Studios, PLLC VHB 13755 Thompson Place Drive 101 Walnut Street Mint Hill, NC 28227 704.578.2851

Geotechnical: GeoEngineers, Inc. 239 Causeway Street Boston, MA 02114 617.749.9227

Bedford, NH 03110

603.391.3900

PO Box 9151 Watertown, MA 02471 617.924.1770

Exist.	Prop.		Exist.	Prop.	
		PROPERTY LINE	The state of the s		CONCRETE
		PROJECT LIMIT LINE	[4,2 , 4,7	(,,,)	HEAVY DUTY PAVEMENT
		RIGHT-OF-WAY/PROPERTY LINE			BUILDINGS
		EASEMENT			RIPRAP
		BUILDING SETBACK			CONSTRUCTION EXIT
		PARKING SETBACK			
10+00	10+00	BASELINE	27.35 TC ×	27.35 TC ×	TOP OF CURB ELEVATION
		CONSTRUCTION LAYOUT	26.85 BC×	26.85 BC×	BOTTOM OF CURB ELEVATION
		ZONING LINE	132.75 × 45.0 TW _×	132.75 × 45.0 TW	SPOT ELEVATION
		TOWN LINE	38.5 BW ×	45.0 TW × 38.5 BW	TOP & BOTTOM OF WALL ELEVATION
		LIMIT OF DISTURBANCE			BORING LOCATION
		LIMIT OF DISTURBANCE WETLAND LINE WITH FLAG	MW	■ MW	TEST PIT LOCATION MONITORING WELL
		FLOODPLAIN			WONTOKING WELL
		BORDERING LAND SUBJECT	UD	——UD——	UNDERDRAIN
BLSF		TO FLOODING	12"D	12″D→	DRAIN
BZ		WETLAND BUFFER ZONE	6"RD	6″RD—►	ROOF DRAIN
NDZ		NO DISTURB ZONE	12"S FM	12 <u>"</u> S FM	SEWER
200'RA-		200' RIVERFRONT AREA		1 W	FORCE MAIN
		GRAVEL ROAD	—— OHW ——	—— OHW ——	OVERHEAD WIRE
	EOP	EDGE OF PAVEMENT		6"W	WATER
BB	BB	BITUMINOUS BERM	——4"FP——	4"FP	FIRE PROTECTION
BC	BC	BITUMINOUS CURB	717 0	2"DW	DOMESTIC WATER
CC	CC	CONCRETE CURB	3"G	——————————————————————————————————————	GAS
	CG	CURB AND GUTTER	——————————————————————————————————————	——STM——	ELECTRIC
CC	ECC	EXTRUDED CONCRETE CURB	T	T	STEAM TELEPHONE
CC	MCC	MONOLITHIC CONCRETE CURB	FA	FA	FIRE ALARM
CC	PCC	PRECAST CONC. CURB	CATV	—— CATV——	CABLE TV
SGE	SGE	SLOPED GRAN. EDGING			CAULLIA
VGC	VGC	VERT. GRAN. CURB			CATCH BASIN CONCENTRIC
		LIMIT OF CURB TYPE			CATCH BASIN ECCENTRIC
		SAWCUT			DOUBLE CATCH BASIN CONCENTRIC
<u> </u>	1		_		DOUBLE CATCH BASIN ECCENTRIC
(1111111		BUILDING	■	m	GUTTER INLET
](EN	BUILDING ENTRANCE	0	•	DRAIN MANHOLE CONCENTRIC
		LOADING DOCK	=TD=		DRAIN MANHOLE ECCENTRIC TRENCH DRAIN
0	•	BOLLARD	Ľ	<u> </u>	PLUG OR CAP
D	D	DUMPSTER PAD	СО	co	CLEANOUT
0	•	SIGN	>	•	FLARED END SECTION
	=	DOUBLE SIGN		\checkmark	HEADWALL
		Steel Guardrail			CELVED MANUALE CONCENTRIC
		WOOD GUARDRAIL	(S)	•	SEWER MANHOLE CONCENTRIC
			=		SEWER MANHOLE ECCENTRIC
	====	PATH	CS ⊚ WV	CS ● WV	CURB STOP & BOX
$\bigvee \bigvee$	\sim	TREE LINE	•	•	WATER VALVE & BOX
	-xx-	WIRE FENCE	TSV	TSV • ►	TAPPING SLEEVE, VALVE & BOX
-	•	FENCE	↔ HYD	₩ HYD	FIRE DEPARTMENT CONNECTION
		STOCKADE FENCE	©• _WM	©∙ _WM	FIRE HYDRANT
000000	∞	STONE WALL	⊡ PIV ⊚	⊡ PIV ⊚	WATER METER
		RETAINING WALL	(ii)	®	POST INDICATOR VALVE WATER WELL
		STREAM / POND / WATER COURSE DETENTION BASIN	GG		
		HAY BALES	GM	GG O GM	GAS GATE
X	——×——	SILT FENCE	•	GM ⊡	GAS METER
· <:::::> ·	· c:::::> ·	SILT SOCK / STRAW WATTLE	E .	● ^{EMH}	ELECTRIC MANHOLE
		·	- EM	EM ⊡	ELECTRIC METER
4		MINOR CONTOUR	\$	*	LIGHT POLE
——20— —	20	MAJOR CONTOUR	1	● ^{TMH}	TELEPHONE MANHOLE
10	10	PARKING COUNT	Т	T	TRANSFORMER PAD
	©10	COMPACT PARKING STALLS	-0-	-	
DYL	DYL	DOUBLE YELLOW LINE		→ -	UTILITY POLE
SL	SL	STOP LINE	<u>o</u>	• − I	GUY POLE
		CROSSWALK	HH	HH III	GUY WIRE & ANCHOR
		ACCESSIBLE CURB RAMP	D PB ⊡	⊡ PB ⊡	HAND HOLE
Ł.	<u> </u>	ACCESSIBLE PARKING			PULL BOX
Ė.	<u>گ</u> ر	VAN-ACCESSIBLE PARKING			

Abbreviations

General	
ABAN	ABANDON
ACR	ACCESSIBLE CURB RAMP
ADJ	ADJUST
APPROX	APPROXIMATE
BIT	BITUMINOUS
BS	BOTTOM OF SLOPE
BWLL	BROKEN WHITE LANE LINE
CONC	CONCRETE
DYCL	DOUBLE YELLOW CENTER LINE
EL	ELEVATION
ELEV	ELEVATION
EX	EXISTING
FDN	FOUNDATION
FFE	FIRST FLOOR ELEVATION
GRAN	GRANITE
GTD	GRADE TO DRAIN
LA	LANDSCAPE AREA
LOD	LIMIT OF DISTURBANCE
MAX	MAXIMUM
MIN	MINIMUM
NIC	NOT IN CONTRACT
NTS	NOT TO SCALE
PERF	PERFORATED
	PROPOSED
REM	REMOVE
RET	RETAIN
R&D	REMOVE AND DISPOSE
R&R	REMOVE AND RESET
SWEL	SOLID WHITE EDGE LINE
SWLL	SOLID WHITE LANE LINE
TS	TOP OF SLOPE
TYP	TYPICAL
Utility	
 Utility	CATCH RASIN
СВ	CATCH BASIN
CB CMP	CORRUGATED METAL PIPE
CB CMP	CORRUGATED METAL PIPE CLEANOUT
CB CMP CO DCB	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN
CB CMP CO DCB DMH	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE
CB CMP CO DCB DMH CIP	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE
CB CMP CO DCB DMH CIP COND	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT
CB CMP CO DCB DMH CIP COND	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE
CB CMP CO DCB DMH CIP COND	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT
CB CMP CO DCB DMH CIP COND DIP FES	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE
CB CMP CO DCB DMH CIP COND DIP FES FM	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION
CB CMP CO DCB DMH CIP COND DIP FES FM F&G	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP MES	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION LIGHT POLE
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP MES PIV	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION LIGHT POLE METAL END SECTION
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP MES PIV PWW	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION LIGHT POLE METAL END SECTION POST INDICATOR VALVE
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP MES PIV PWW PVC	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION INVERT ELEVATION LIGHT POLE METAL END SECTION POST INDICATOR VALVE PAVED WATER WAY POLYVINYLCHLORIDE PIPE
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP MES PIV PWW PVC RCP	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION LIGHT POLE METAL END SECTION POST INDICATOR VALVE PAVED WATER WAY POLYVINYLCHLORIDE PIPE REINFORCED CONCRETE PIPE
CB CMP CO DCB DMH CIP COND DIP FES FM F&G GT HDPE HH HW HYD INV I= LP MES PIV PWW PVC RCP R=	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION LIGHT POLE METAL END SECTION POST INDICATOR VALVE PAVED WATER WAY POLYVINYLCHLORIDE PIPE RIM ELEVATION
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP MES PIV PWW PVC RCP R= RIM=	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION INVERT ELEVATION LIGHT POLE METAL END SECTION POST INDICATOR VALVE PAVED WATER WAY POLYVINYLCHLORIDE PIPE REINFORCED CONCRETE PIPE RIM ELEVATION RIM ELEVATION RIM ELEVATION
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP MES PIV PWW PVC RCP R= RIM= SMH	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION LIGHT POLE METAL END SECTION POST INDICATOR VALVE PAVED WATER WAY POLYVINYLCHLORIDE PIPE RIM ELEVATION RIM ELEVATION RIM ELEVATION RIM ELEVATION RIM ELEVATION RIM ELEVATION SEWER MANHOLE
CB CMP CO DCB DMH CIP COND DIP FES FM F&G F&C GI GT HDPE HH HW HYD INV I= LP MES PIV PWW PVC RCP R= RIM= SMH TSV	CORRUGATED METAL PIPE CLEANOUT DOUBLE CATCH BASIN DRAIN MANHOLE CAST IRON PIPE CONDUIT DUCTILE IRON PIPE FLARED END SECTION FORCE MAIN FRAME AND GRATE FRAME AND COVER GUTTER INLET GREASE TRAP HIGH DENSITY POLYETHYLENE PIPE HANDHOLE HEADWALL HYDRANT INVERT ELEVATION INVERT ELEVATION LIGHT POLE METAL END SECTION POST INDICATOR VALVE PAVED WATER WAY POLYVINYLCHLORIDE PIPE REINFORCED CONCRETE PIPE RIM ELEVATION RIM ELEVATION RIM ELEVATION

UTILITY POLE

Notes

General

- 1. CONTRACTOR SHALL NOTIFY "DIG-SAFE" (1-888-344-7233) AT LEAST 72 HOURS BEFORE EXCAVATING.
- CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SECURITY AND JOB SAFETY. CONSTRUCTION ACTIVITIES SHALL BE IN ACCORDANCE WITH OSHA STANDARDS AND LOCAL REQUIREMENTS.
- 3. ACCESSIBLE ROUTES, PARKING SPACES, RAMPS, SIDEWALKS AND WALKWAYS SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE FEDERAL AMERICANS WITH DISABILITIES ACT AND WITH STATE AND LOCAL LAWS AND REGULATIONS (WHICHEVER ARE MORE STRINGENT).
- 4. AREAS DISTURBED DURING CONSTRUCTION AND NOT RESTORED WITH IMPERVIOUS SURFACES (BUILDINGS, PAVEMENTS, WALKS, ETC.) SHALL RECEIVE 6" INCHES LOAM AND SEED.
- 5. WITHIN THE LIMITS OF THE BUILDING FOOTPRINT, THE SITE CONTRACTOR SHALL PERFORM EARTHWORK OPERATIONS REQUIRED UP TO SUBGRADE ELEVATIONS.
- 6. WORK WITHIN THE LOCAL RIGHTS-OF-WAY SHALL CONFORM TO LOCAL MUNICIPAL STANDARDS. WORK WITHIN STATE RIGHTS-OF-WAY SHALL CONFORM TO THE LATEST EDITION OF THE STATE HIGHWAY DEPARTMENTS STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES
- HIGHWAY DEPARTMENTS STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES.

 7. UPON AWARD OF CONTRACT, CONTRACTOR SHALL MAKE NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN NECESSARY PERMITS, PAY FEES, AND POST BONDS ASSOCIATED WITH THE WORK INDICATED ON THE DRAWINGS. IN THE SPECIFICATIONS. AND IN THE CONTRACT

DOCUMENTS. DO NOT CLOSE OR OBSTRUCT ROADWAYS, SIDEWALKS, AND FIRE HYDRANTS, WITHOUT

- 8. TRAFFIC SIGNAGE AND PAVEMENT MARKINGS SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- 9. AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S
- 10. IN THE EVENT THAT SUSPECTED CONTAMINATED SOIL, GROUNDWATER, AND OTHER MEDIA ARE ENCOUNTERED DURING EXCAVATION AND CONSTRUCTION ACTIVITIES BASED ON VISUAL, OLFACTORY, OR OTHER EVIDENCE, THE CONTRACTOR SHALL STOP WORK IN THE VICINITY OF THE SUSPECT MATERIAL TO AVOID FURTHER SPREADING OF THE MATERIAL, AND SHALL NOTIFY THE OWNER IMMEDIATELY SO THAT THE APPROPRIATE TESTING AND SUBSEQUENT ACTION CAN BE TAKEN.
- 11. CONTRACTOR SHALL PREVENT DUST, SEDIMENT, AND DEBRIS FROM EXITING THE SITE AND SHALL BE RESPONSIBLE FOR CLEANUP, REPAIRS AND CORRECTIVE ACTION IF SUCH OCCURS.
- 12. DAMAGE RESULTING FROM CONSTRUCTION LOADS SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO OWNER.
- 13. CONTRACTOR SHALL CONTROL STORMWATER RUNOFF DURING CONSTRUCTION TO PREVENT ADVERSE IMPACTS TO OFF SITE AREAS, AND SHALL BE RESPONSIBLE TO REPAIR RESULTING DAMAGES, IF ANY, AT NO COST TO OWNER.

Utilitie

- 1. THE LOCATIONS, SIZES, AND TYPES OF EXISTING UTILITIES ARE SHOWN AS AN APPROXIMATE REPRESENTATION ONLY. THE OWNER OR ITS REPRESENTATIVE(S) HAVE NOT INDEPENDENTLY VERIFIED THIS INFORMATION AS SHOWN ON THE PLANS. THE UTILITY INFORMATION SHOWN DOES NOT GUARANTEE THE ACTUAL EXISTENCE, SERVICEABILITY, OR OTHER DATA CONCERNING THE UTILITIES, NOR DOES IT GUARANTEE AGAINST THE POSSIBILITY THAT ADDITIONAL UTILITIES MAY BE PRESENT THAT ARE NOT SHOWN ON THE PLANS. PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY AND DETERMINE THE EXACT LOCATIONS, SIZES, AND ELEVATIONS OF THE POINTS OF CONNECTIONS TO EXISTING UTILITIES AND, SHALL CONFIRM THAT THERE ARE NO INTERFERENCES WITH EXISTING UTILITIES AND THE PROPOSED UTILITY ROUTES, INCLUDING ROUTES WITHIN THE PUBLIC RIGHTS OF WAY.
- WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, OR EXISTING CONDITIONS DIFFER FROM THOSE SHOWN SUCH THAT THE WORK CANNOT BE COMPLETED AS INTENDED, THE LOCATION, ELEVATION, AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED IN WRITING TO THE OWNER'S REPRESENTATIVE FOR THE RESOLUTION OF THE CONFLICT AND CONTRACTOR'S FAILURE TO NOTIFY PRIOR TO PERFORMING ADDITIONAL WORK RELEASES OWNER FROM OBLIGATIONS FOR ADDITIONAL PAYMENTS WHICH OTHERWISE MAY BE WARRANTED TO RESOLVE THE CONFLICT.
- 3. SET CATCH BASIN RIMS, AND INVERTS OF SEWERS, DRAINS, AND DITCHES IN ACCORDANCE WITH ELEVATIONS ON THE GRADING AND UTILITY PLANS.
- 4. RIM ELEVATIONS FOR DRAIN AND SEWER MANHOLES, WATER VALVE COVERS, GAS GATES, ELECTRIC AND TELEPHONE PULL BOXES, AND MANHOLES, AND OTHER SUCH ITEMS, ARE APPROXIMATE AND SHALL BE SET/RESET AS FOLLOWS:
 - A. PAVEMENTS AND CONCRETE SURFACES: FLUSH
 - B. ALL SURFACES ALONG ACCESSIBLE ROUTES: FLUSH

THE UTILITIES COMPANY.

- C. LANDSCAPE, LOAM AND SEED, AND OTHER EARTH SURFACE AREAS: ONE INCH ABOVE SURROUNDING AREA AND TAPER EARTH TO THE RIM ELEVATION.
- 5. THE LOCATION, SIZE, DEPTH, AND SPECIFICATIONS FOR CONSTRUCTION OF PROPOSED PRIVATE UTILITY SERVICES SHALL BE INSTALLED ACCORDING TO THE REQUIREMENTS PROVIDED BY, AND APPROVED BY, THE RESERVE USE OF THE PROPOSED FOR THE PROPO
- LOADS AND LOCATIONS TO BE COORDINATED WITH OWNER AND ARCHITECT.

 6. CONTRACTOR SHALL MAKE ARRANGEMENTS FOR AND SHALL BE RESPONSIBLE FOR PAYING FEES FOR POLE RELOCATION AND FOR THE ALTERATION AND ADJUSTMENT OF GAS, ELECTRIC, TELEPHONE, FIRE ALARM, AND ANY OTHER PRIVATE UTILITIES, WHETHER WORK IS PERFORMED BY CONTRACTOR OR BY
- 7. UTILITY PIPE MATERIALS SHALL BE AS FOLLOWS, UNLESS OTHERWISE NOTED ON THE PLAN:
 - A. WATER PIPES SHALL BE CEMENT LINED DUCTILE IRON (DI) CLASS 52.
 - B. SANITARY SEWER PIPES SHALL BE POLYVINYL CHLORIDE (PVC) SEWER PIPE, SDR-35
 - C. STORM DRAINAGE PIPES SHALL BE HIGH DENSITY POLYETHYLENE (HDPE).
 - D. PIPE INSTALLATION AND MATERIALS SHALL COMPLY WITH THE STATE PLUMBING CODE WHERE APPLICABLE. CONTRACTOR SHALL COORDINATE WITH LOCAL PLUMBING INSPECTOR PRIOR TO BEGINNING WORK.
- 8. CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR AND SHALL FURNISH EXCAVATION, INSTALLATION, AND BACKFILL OF ELECTRICAL FURNISHED SITEWORK RELATED ITEMS SUCH AS PULL BOXES, CONDUITS, DUCT BANKS, LIGHT POLE BASES, AND CONCRETE PADS. SITE CONTRACTOR SHALL FURNISH CONCRETE ENCASEMENT OF DUCT BANKS IF REQUIRED BY THE UTILITY COMPANY AND AS INDICATED ON THE DRAWINGS.
- 9. CONTRACTOR SHALL EXCAVATE AND BACKFILL TRENCHES FOR GAS IN ACCORDANCE WITH GAS COMPANY'S REQUIREMENTS.
- 10. ALL DRAINAGE AND SANITARY STRUCTURE INTERIOR DIAMETERS (4' MIN.) SHALL BE DETERMINED BY THE MANUFACTURER BASED ON THE PIPE CONFIGURATIONS SHOWN ON THESE PLANS AND LOCAL MUNICIPAL STANDARDS. FOR MANHOLES THAT ARE 20 FEET IN DEPTH AND GREATER, THE MINIMUM DIAMETER SHALL BE 5 FEET.

Layout and Materials

- 1. DIMENSIONS ARE FROM THE FACE OF CURB, FACE OF BUILDING, FACE OF WALL, AND CENTER LINE OF PAVEMENT MARKINGS, UNLESS OTHERWISE NOTED.
- 2. CURB RADII ARE 3 FEET UNLESS OTHERWISE NOTED.
- CURBING SHALL BE PRECAST CONCRETE CURB (PCC) WITHIN THE SITE UNLESS OTHERWISE INDICATED ON THE PLANS.
- 4. SEE ARCHITECTURAL DRAWINGS FOR EXACT BUILDING DIMENSIONS AND DETAILS CONTIGUOUS TO THE BUILDING, INCLUDING SIDEWALKS, RAMPS, BUILDING ENTRANCES, STAIRWAYS, UTILITY PENETRATIONS, CONCRETE DOOR PADS, COMPACTOR PAD, LOADING DOCKS, BOLLARDS, ETC.
- 5. PROPOSED BOUNDS AND ANY EXISTING PROPERTY LINE MONUMENTATION DISTURBED DURING CONSTRUCTION SHALL BE SET OR RESET BY A PROFESSIONAL LAND SURVEYOR.
- 6. PRIOR TO START OF CONSTRUCTION, CONTRACTOR SHALL VERIFY EXISTING PAVEMENT ELEVATIONS AT INTERFACE WITH PROPOSED PAVEMENTS, AND EXISTING GROUND ELEVATIONS ADJACENT TO DRAINAGE OUTLETS TO ASSURE PROPER TRANSITIONS BETWEEN EXISTING AND PROPOSED FACILITIES.

Demolition

- CONTRACTOR SHALL REMOVE AND DISPOSE OF EXISTING MANMADE SURFACE FEATURES WITHIN THE LIMIT OF WORK INCLUDING BUILDINGS, STRUCTURES, PAVEMENTS, SLABS, CURBING, FENCES, UTILITY POLES, SIGNS, ETC. UNLESS INDICATED OTHERWISE ON THE DRAWINGS. REMOVE AND DISPOSE OF EXISTING UTILITIES, FOUNDATIONS AND UNSUITABLE MATERIAL BENEATH AND FOR A DISTANCE OF 10 FEET BEYOND THE PROPOSED BUILDING FOOTPRINT INCLUDING EXTERIOR COLUMNS.
- 2. EXISTING UTILITIES SHALL BE TERMINATED, UNLESS OTHERWISE NOTED, IN CONFORMANCE WITH LOCAL, STATE AND INDIVIDUAL UTILITY COMPANY STANDARD SPECIFICATIONS AND DETAILS. THE CONTRACTOR SHALL COORDINATE UTILITY SERVICE DISCONNECTS WITH THE UTILITY REPRESENTATIVES.
- 3. CONTRACTOR SHALL DISPOSE OF DEMOLITION DEBRIS IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS, ORDINANCES AND STATUTES.
- THE DEMOLITION LIMITS DEPICTED IN THE PLANS IS INTENDED TO AID THE CONTRACTOR DURING THE BIDDING AND CONSTRUCTION PROCESS AND IS NOT INTENDED TO DEPICT EACH AND EVERY ELEMENT OF DEMOLITION. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING THE DETAILED SCOPE OF DEMOLITION BEFORE SUBMITTING ITS BID/PROPOSAL TO PERFORM THE WORK AND SHALL MAKE NO CLAIMS AND SEEK NO ADDITIONAL COMPENSATION FOR CHANGED CONDITIONS OR UNFORESEEN OR LATENT SITE CONDITIONS RELATED TO ANY CONDITIONS DISCOVERED DURING EXECUTION OF THE WORK
- 5. UNLESS OTHERWISE SPECIFICALLY PROVIDED ON THE PLANS OR IN THE SPECIFICATIONS, THE ENGINEER HAS NOT PREPARED DESIGNS FOR AND SHALL HAVE NO RESPONSIBILITY FOR THE PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF HAZARDOUS MATERIALS, TOXIC WASTES OR POLLUTANTS AT THE PROJECT SITE. THE ENGINEER SHALL NOT BE RESPONSIBLE FOR ANY CLAIMS OF LOSS, DAMAGE, EXPENSE, DELAY, INJURY OR DEATH ARISING FROM THE PRESENCE OF HAZARDOUS MATERIAL AND CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE ENGINEER FROM ANY CLAIMS MADE IN CONNECTION THEREWITH. MOREOVER, THE ENGINEER SHALL HAVE NO ADMINISTRATIVE OBLIGATIONS OF ANY TYPE WITH REGARD TO ANY CONTRACTOR AMENDMENT INVOLVING THE ISSUES OF PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF ASBESTOS OR OTHER HAZARDOUS MATERIALS.

Erosion Control

- 1. PRIOR TO STARTING ANY OTHER WORK ON THE SITE, THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES AND SHALL INSTALL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS IDENTIFIED IN FEDERAL, STATE, AND LOCAL APPROVAL DOCUMENTS PERTAINING TO THIS PROJECT.
- 2. CONTRACTOR SHALL INSPECT AND MAINTAIN EROSION CONTROL MEASURES ON A WEEKLY BASIS (MINIMUM) OR AS REQUIRED PER THE ORDER OF CONDITIONS. THE CONTRACTOR SHALL ADDRESS DEFICIENCIES AND MAINTENANCE ITEMS WITHIN TWENTY-FOUR HOURS OF INSPECTION. CONTRACTOR SHALL PROPERLY DISPOSE OF SEDIMENT SUCH THAT IT DOES NOT ENCUMBER OTHER DRAINAGE STRUCTURES AND PROTECTED AREAS.
- 3. CONTRACTOR SHALL BE FULLY RESPONSIBLE TO CONTROL CONSTRUCTION SUCH THAT SEDIMENTATION SHALL NOT AFFECT REGULATORY PROTECTED AREAS, WHETHER SUCH SEDIMENTATION IS CAUSED BY WATER, WIND, OR DIRECT DEPOSIT.
- 4. CONTRACTOR SHALL PERFORM CONSTRUCTION SEQUENCING SUCH THAT EARTH MATERIALS ARE EXPOSED FOR A MINIMUM OF TIME BEFORE THEY ARE COVERED, SEEDED, OR OTHERWISE STABILIZED TO REFUGNITION.
- 5. UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF PERMANENT GROUND COVER, CONTRACTOR SHALL REMOVE AND DISPOSE OF EROSION CONTROL MEASURES AND CLEAN SEDIMENT AND DEBRIS FROM ENTIRE DRAINAGE AND SEWER SYSTEMS.
- 6. CONTRACTOR TO PROVIDE CONTAINMENT BERM AT TOP OF SLOPE ADJACENT TO MILL BROOK TO PREVENT RUNOFF FROM CONSTRUCTION ACTIVITIES DISCHARGING TOWARDS MILL BROOK.

Existing Conditions Information

- 1. BASE PLAN: THE PROPERTY LINES SHOWN ON THE LAYOUT AND MATERIALS PLAN WERE DETERMINED BY AN ACTUAL FIELD SURVEY CONDUCTED BY VHB, INC. IN OCTOBER, 2021, AND FROM DEEDS AND PLANS OF RECORD. THE TOPOGRAPHY AND PHYSICAL FEATURES ARE BASED ON AN ACTUAL FIELD SURVEY PERFORMED ON THE GROUND BY VHB, INC., DURING OCTOBER, 2021.
 - A. DELINEATION OF THE WETLANDS AND PLACEMENT OF THE FLAGS WAS PERFORMED BY: VHB ENVIRONMENTAL DEPARTMENT IN OCTOBER, 2021.
 - B. FLAGS MARKING THE WETLANDS WERE LOCATED BY: VHB, BY FIELD SURVEY IN OCTOBER, 2021
- 2. TOPOGRAPHY: ELEVATIONS ARE BASED ON NAVD OF 1988.
- GEOTECHNICAL DATA INCLUDING TEST PIT AND BORING LOCATIONS AND ELEVATIONS WERE OBTAINED FROM GEOENGINEERS USA, PC DATED JANUARY 28, 2022.

Document Use

- 1. THESE PLANS AND CORRESPONDING CADD DOCUMENTS ARE INSTRUMENTS OF PROFESSIONAL SERVICE, AND SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE OTHER THAN FOR WHICH IT WAS CREATED WITHOUT THE EXPRESSED, WRITTEN CONSENT OF VHB. ANY UNAUTHORIZED USE, REUSE, MODIFICATION OR ALTERATION, INCLUDING AUTOMATED CONVERSION OF THIS DOCUMENT SHALL BE AT THE USER'S SOLE RISK WITHOUT LIABILITY OR LEGAL EXPOSURE TO VHB.
- 2. CONTRACTOR SHALL NOT RELY SOLELY ON ELECTRONIC VERSIONS OF PLANS, SPECIFICATIONS, AND DATA FILES THAT ARE OBTAINED FROM THE DESIGNERS, BUT SHALL VERIFY LOCATION OF PROJECT FEATURES IN ACCORDANCE WITH THE PAPER COPIES OF THE PLANS AND SPECIFICATIONS THAT ARE SUPPLIED AS PART OF THE CONTRACT DOCUMENTS.
- 3. SYMBOLS AND LEGENDS OF PROJECT FEATURES ARE GRAPHIC REPRESENTATIONS AND ARE NOT NECESSARILY SCALED TO THEIR ACTUAL DIMENSIONS OR LOCATIONS ON THE DRAWINGS. THE CONTRACTOR SHALL REFER TO THE DETAIL SHEET DIMENSIONS, MANUFACTURERS' LITERATURE, SHOP DRAWINGS AND FIELD MEASUREMENTS OF SUPPLIED PRODUCTS FOR LAYOUT OF THE PROJECT FEATURES.



PO Box 9151 Watertown, MA 02471 617.924.1770


Proposed Self-Storage Facility

34 Dudley St Arlington, Massachusetts 02476

No.	Revision	Date	Appvd
1	ARB COMMENTS	4/21/2022	EKG

	February 9, 202
Issued for	Date
Designed by MEA	Checked by EKG

Not Approved for Construction





ct Number

THE PROPOSED PROJECT CONSISTS OF A 95,700± SQUARE-FOOT SELF STORAGE FACILITY WITH ANCILLARY LANDSCAPE IMPROVEMENTS, PARKING SPACES, AND UTILITY IMPROVEMENTS TO SUPPORT THIS USE. THE

APPROXIMATELY 0.78 ACRE SITE WILL BE DEVELOPED AS A SINGLE-PHASE PROJECT.

BE PLACED IN THE ENTRANCE TO DIRECT RUNOFF TO THE SEDIMENT TRAP.

EROSION AND SEDIMENTATION CONTROL TECHNIQUES

THE EROSION AND SEDIMENTATION CONTROLS SHOWN HEREON ARE PERIMETER MEASURES ONLY. THE CONTRACTOR IS REQUIRED TO PROVIDE ADDITIONAL INTERIM EROSION AND SEDIMENTATION CONTROLS, INCLUDING BUT NOT LIMITED TO THOSE LISTED BELOW. THE CONTRACTOR SHALL MANAGE EROSION AND SEDIMENTATION DURING CONSTRUCTION TO PREVENT IMPACTS TO RESOURCE AREAS, ROADWAYS, AND ABUTTING PROPERTIES. THE CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN THE EROSION AND SEDIMENTATION CONTROLS THROUGHOUT THE DURATION OF CONSTRUCTION.

NEWLY CONSTRUCTED AND EXISTING CATCH BASINS WILL BE PROTECTED WITH SILT SACKS THROUGHOUT CONSTRUCTION.

GRAVEL AND CONSTRUCTION ENTRANCE/EXIT
A TEMPORARY CRUSHED-STONE CONSTRUCTION ENTRANCE/EXIT WILL BE CONSTRUCTED. A CROSS SLOPE WILL

STABILIZATION OF OPEN SOIL SURFACES WILL BE IMPLEMENTED WITHIN 14 DAYS AFTER GRADING OR CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, UNLESS THERE IS SUFFICIENT SNOW COVER TO PROHIBIT IMPLEMENTATION. VEGETATIVE SLOPE STABILIZATION WILL BE USED TO MINIMIZE EROSION ON SLOPES OF 3:1 OR FLATTER. ANNUAL GRASSES, SUCH AS ANNUAL RYE, WILL BE USED TO ENSURE RAPID GERMINATION AND PRODUCTION OF ROOTMASS. PERMANENT STABILIZATION WILL BE COMPLETED WITH THE PLANTING OF PERENNIAL GRASSES OR LEGUMES. ESTABLISHMENT OF TEMPORARY AND PERMANENT VEGETATIVE COVER MAY BE ESTABLISHED BY HYDRO-SEEDING OR SODDING. A SUITABLE TOPSOIL, GOOD SEEDBED PREPARATION, AND ADEQUATE LIME, FERTILIZER AND WATER WILL BE PROVIDED FOR EFFECTIVE ESTABLISHMENT OF THESE VEGETATIVE STABILIZATION METHODS. MULCH WILL ALSO BE USED AFTER PERMANENT SEEDING TO PROTECT SOIL FROM THE IMPACT OF FALLING RAIN AND TO INCREASE THE CAPACITY OF THE SOIL TO ABSORB

TEMPORARY SEDIMENT BASINS WILL BE DESIGNED EITHER AS EXCAVATIONS OR BERMED STORMWATER DETENTION STRUCTURES (DEPENDING ON GRADING) THAT WILL RETAIN RUNOFF FOR A SUFFICIENT PERIOD OF TIME TO ALLOW SUSPENDED SOIL PARTICLES TO SETTLE OUT PRIOR TO DISCHARGE. THESE TEMPORARY BASINS WILL BE LOCATED BASED ON CONSTRUCTION NEEDS AS DETERMINED BY THE CONTRACTOR AND OUTLET DEVICES WILL BE DESIGNED TO CONTROL VELOCITY AND SEDIMENT. POINTS OF DISCHARGE FROM SEDIMENT BASINS WILL BE STABILIZED TO MINIMIZE EROSION. AT A MINIMUM, SEDIMENTATION BASINS SHALL BE DESIGNED AND CONSTRUCTED TO PROVIDE STORAGE FOR THE VOLUME OF RUNOFF GENERATED FROM A 2-YR, 24-HR DESIGN STORM, OR AT LEAST 3,600 CUBIC FEET OF STORAGE PER ACRE DRAINING TO THE BASIN.

SIDESLOPES OF STOCKPILED MATERIAL SHALL BE NO STEEPER THAN 2:1. STOCKPILES NOT USED WITHIN 30 DAYS NEED TO BE SEEDED AND MULCHED IMMEDIATELY AFTER FORMATION OF THE STOCKPILE. STRAW BALES AND SILT FENCE ARE TO BE PLACED AROUND THE STOCKPILE AREA APPROXIMATELY 10 FEET FROM THE TOE OF SLOPE.

PERIODICALLY MOISTEN EXPOSED SURFACES ON UNPAVED TRAVELWAYS TO KEEP THE TRAVELWAY DAMP AND

TEMPORARY EROSION AND SEDIMENTATION CONTROL MAINTENANCE (THROUGHOUT CONSTRUCTION)

THE SITE CONTRACTOR SHALL INSPECT AND MAINTAIN EROSION CONTROL MEASURES ON A WEEKLY BASIS (MINIMUM) OR AS REQUIRED PER ORDER OF CONDITIONS. THE CONTRACTOR SHALL ADDRESS DEFICIENCIES AND MAINTENANCE ITEMS WITHIN TWENTY-FOUR HOURS OF INSPECTION. CONTRACTOR SHALL PROPERLY DISPOSE OF SEDIMENT SUCH THAT IT DOES NOT ENCUMBER OTHER DRAINAGE STRUCTURES AND PROTECTED AREAS. RECORDS OF THE INSPECTIONS WILL BE PREPARED AND MAINTAINED ON-SITE BY THE CONTRACTOR.

SILT SHALL BE REMOVED FROM BEHIND BARRIERS IF GREATER THAN 6-INCHES DEEP OR AS NEEDED.

DAMAGED OR DETERIORATED ITEMS WILL BE REPAIRED IMMEDIATELY AFTER IDENTIFICATION.

SEDIMENT THAT IS COLLECTED IN STRUCTURES SHALL BE DISPOSED OF PROPERLY AND COVERED IF STORED

EROSION CONTROL STRUCTURES SHALL REMAIN IN PLACE UNTIL ALL DISTURBED EARTH HAS BEEN SECURELY STABILIZED. AFTER REMOVAL OF STRUCTURES, DISTURBED AREAS SHALL BE REGRADED AND STABILIZED AS SOON

MAINTAIN THE CONSTRUCTION ENTRANCE IN A CONDITION WHICH WILL PREVENT TRACKING AND WASHING OF SEDIMENTS ONTO PAVED SURFACES.

DEMOLISH EXIST STRUCTURES (TYP) -

INFILTRATION AREA PROTECTION DURING CONSTRUCTION

FOR THE LONG-TERM FUNCTION OF THE INFILTRATION BASIN(S)/STRUCTURE(S), CARE SHALL BE TAKEN IN THE INFILTRATION AREAS DURING CONSTRUCTION THE CONSTRACTOR SHALL EMPLOY THE FOLLOWING MINIMUM BEST MANAGEMENT PRACTICES (BMPS):

- 1. INFILTRATION AREAS SHALL NOT BE USED AS TEMPORARY CONSTRUCTION SEDIMENTATION BASINS WITHOUT THE PRIOR APPROVAL OF THE ENGINEER. IF INFILTRATION AREAS ARE USED AS TEMPORARY SEDIMENTATION BASINS DURING CONSTRUCTION, THEN THE SOILS SHALL BE EXCAVATED A MINIMUM OF 2' FROM THE TEMPORARY BASIN BOTTOM TO REMOVE CLOGGED SOILS.
- 2. STORMWATER RUNOFF FROM EXPOSED SURFACES SHALL BE DIRECTED AWAY FROM THE INFILTRATION BASIN(S)/STRUCTURE(S) DURING CONSTRUCTION
- 3. CONSTRUCTION EQUIPMENT, VEHICULAR TRAFFIC, PARKING OF VEHICLES, AND STOCKPILING OF CONSTRUCTION MATERIALS SHALL BE LOCATED OUTSIDE OF THE INFILTRATION AREAS.
- 4. EXCAVATION FOR CONSTRUCTION OF THE INFILTRATION BASIN(S)/STRUCTURE(S) SHALL ENSURE THAT THE SOIL AT THE BOTTOM OF THE EXCAVATION IS NOT COMPACTED OR SMEARED.
- 5. THE PERIMETER OF THE INFILTRATION AREAS SHALL BE STAKED AND FLAGGED TO PREVENT THE USE OF THE

PROTECTION (TYP)

CAP EXIST WATER SERVICE,


COORDINATE WITH DPW -

CAP EXIST GAS, COORDINATE WITH PRIVATE UTILITY -

CONTRACTOR TO PROVIDE

EXIT (SEE DETAIL) -

STABILIZED CONSTRUCTION



- REMOVE EXIST FENCE

CONTRACTOR TO PROVIDE TEMPORARY MEASURES FOR PEDESTRIANS DURING CONSTRUCTION AS NECESSARY. COORD WITH TOWN OF ARLINGTON

APPROX EXIST SEWER SERVICE LOCATION. CONTRACTOR

TO FIELD VERITY AND CAP FOR PROJECT USE, IF POSSIBLE

REMOVE EXIST SIGN,

LIGHTS, AND WOOD WALL

Site Preparation Notes:


- UNLESS OTHERWISE SPECIFICALLY PROVIDED ON THE PLANS OR IN THE SPECIFICATIONS, THE ENGINEER HAS NOT PREPARED DESIGNS FOR AND SHALL HAVE NO RESPONSIBILITY FOR THE PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF HAZARDOUS MATERIALS, TOXIC WASTES OR POLLUTANTS AT THE PROJECT SITE. THE ENGINEER SHALL NOT BE RESPONSIBLE FOR ANY CLAIMS OF LOSS, DAMAGE, EXPENSE, DELAY, INJURY OR DEATH ARISING FROM THE PRESENCE OF HAZARDOUS MATERIAL AND CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE ENGINEER FROM ANY CLAIMS MADE IN CONNECTION THEREWITH. MOREOVER, THE ENGINEER SHALL HAVE NO ADMINISTRATIVE OBLIGATIONS OF ANY TYPE WITH REGARD TO ANY CONTRACTOR AMENDMENT INVOLVING THE ISSUES OF PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF ASBESTOS OR OTHER
- CONTRACTOR SHALL REMOVE AND DISPOSE OF EXISTING MANMADE SURFACE FEATURES WITHIN THE LIMIT OF DEMOLITION INCLUDING BUILDINGS, STRUCTURES, PAVEMENTS, SLABS, CURBING, FENCES, UTILITY POLES, SIGNS, ETC. UNLESS INDICATED
- THE LOCATIONS, SIZES, AND TYPES OF EXISTING UTILITIES ARE SHOWN AS AN APPROXIMATE REPRESENTATION ONLY. THE OWNER OR IT'S REPRESENTATIVE(S) HAVE NOT INDEPENDENTLY VERIFIED THIS INFORMATION AS SHOWN ON THE PLANS. THE UTILITY INFORMATION SHOWN DOES NOT GUARANTEE THE ACTUAL EXISTENCE, SERVICEABILITY, OR OTHER DATA CONCERNING THE UTILITIES, NOR DOES IT GUARANTEE AGAINST THE POSSIBILITY THAT ADDITIONAL UTILITIES MAY BE PRESENT THAT ARE NOT SHOWN ON THE PLANS. PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY AND DETERMINE THE EXACT LOCATIONS, SIZES, AND ELEVATIONS OF THE POINTS OF CONNECTIONS TO EXISTING UTILITIES AND, SHALL CONFIRM THAT THERE ARE NO INTERFERENCES WITH EXISTING UTILITIES AND THE PROPOSED UTILITY ROUTES, INCLUDING ROUTES WITHIN THE PUBLIC RIGHTS OF WAY.
- EXISTING UTILITIES SHALL BE TERMINATED, UNLESS OTHERWISE NOTED, IN CONFORMANCE WITH LOCAL, STATE AND INDIVIDUAL UTILITY COMPANY STANDARD SPECIFICATIONS AND DETAILS. THE CONTRACTOR SHALL COORDINATE UTILITY SERVICE DISCONNECTS WITH THE UTILITY REPRESENTATIVES.
- CONTRACTOR SHALL DISPOSE OF DEMOLITION DEBRIS IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS, ORDINANCES AND STATUTES.
- THE DEMOLITION LIMITS DEPICTED IS INTENDED TO AID THE CONTRACTOR DURING THE BIDDING AND CONSTRUCTION PROCESS AND IS NOT INTENDED TO DEPICT EACH AND EVERY ELEMENT OF DEMOLITION. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING THE DETAILED SCOPE OF DEMOLITION BEFORE SUBMITTING ITS BID/PROPOSAL TO PERFORM THE WORK AND SHALL MAKE NO CLAIMS AND SEEK NO ADDITIONAL COMPENSATION FOR CHANGED CONDITIONS OR UNFORESEEN OR LATENT SITE CONDITIONS RELATED TO ANY CONDITIONS DISCOVERED DURING EXECUTION OF THE WORK.
- EXISTING UTILITIES AND FEATURES TO REMAIN SHALL BE MAINTAINED AND PROTECTED AGAINST DAMAGE DURING DEMOLITION
- EXISTING UTILITY LINES NOT SPECIFICALLY NOTED OR SHOWN WHICH ARE ENCOUNTERED DURING CONSTRUCTION SHALL BE CAPPED, EXTENDED, PROTECTED, REMOVED, OR REWORKED AS DIRECTED OR REQUIRED BY THE OWNER OR THE TOWN OF
- 9. CM/CONTRACTOR SHALL APPLY FOR AND OBTAIN ALL NECESSARY PERMITS FROM LOCAL AND STATE AUTHORITIES TO COMPLETE
- 10. CM/CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE AND FEDERAL SAFETY REGULATIONS TO PROTECT THE PUBLIC WHILE DEMOLITION WORK IS BEING PERFORMED.
- 11. FURNISH, ERECT AND MAINTAIN ALL TEMPORARY BARRICADES, FENCES, COVERINGS, ENCLOSURES, SIGNS AND LIGHTING AS MAY BE REQUIRED TO CARRY ON DEMOLITION WORK IN A SAFE AND LEGAL MANNER.
- 12. CATCH BASINS WITHIN THE LIMIT OF WORK AND IN THE IMMEDIATE VICINITY OF THE LIMIT OF WORK SHALL BE FITTED WITH SEDIMENTATION TRAPS UNTIL THE SITE IS PERMANENTLY STABILIZED.
- 13. CM/CONTRACTOR SHALL BE FULLY RESPONSIBLE TO CONTROL CONSTRUCTION SUCH THAT SEDIMENTATION SHALL NOT AFFECT REGULATORY PROTECTED AREAS, WHETHER SUCH SEDIMENTATION IS CAUSED BY WATER, WIND, OR DIRECT DEPOSIT.
- 14. DO NOT USE EXPLOSIVES FOR BUILDING DEMOLITION.
- 15. DUST CONTROL TREATMENTS SHALL BE APPLIED AS NECESSARY TO CONTROL AND REDUCE THE AMOUNT OF DUST WHICH MAY CAUSE OFF SITE DAMAGE, BE A HEALTH HAZARD TO HUMANS, WILDLIFE AND PLANT LIFE, OR POSE A HAZARD TO TRAFFIC SAFETY.
- 16. ADJOINING STREETS AND PROPERTIES SHALL BE KEPT FREE OF DEBRIS RESULTING FROM THE DEMOLITION AND SHALL BE BROOM CLEANED ON A DAILY BASIS.
- 17. HOURS OF OPERATION TO BE AS PER LOCAL ORDINANCE. CM/CONTRACTOR TO VERIFY PRIOR TO STARTING ON SITE OPERATIONS.
- 18. WHERE CONNECTIONS TO EXISTING UTILITIES ARE PROPOSED, THE CM/CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF THE EXISTING UTILITY AT THE CONNECTION POINT PRIOR TO ORDERING MATERIALS OR DEMOLISHING ANY UNUSED PORTIONS OF THE UTILITY AS SPECIFICALLY CALLED OUT ON THIS PLAN. DISCREPANCIES WITH THE EXISTING CONDITIONS INFORMATION SHOWN SHALL BE REPORTED TO THE ENGINEER FOR DIRECTION.
- 19. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING SITE ACCESS AND SITE SECURITY AT ALL TIMES DURING CONSTRUCTION.
- 20. ALL EXISTING TREES WITHIN THE LIMIT OF DEMOLITION SHALL BE REMOVED AND DISPOSED OF OFF SITE AT A SAFE, APPROVED LOCATION UNLESS OTHERWISE NOTED.
- 21. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING CONSTRUCTION EXITS AT ALL CONSTRUCTION VEHICLE ACCESS POINTS ONTO DISTURBED AREAS OF THE SITE. CONSTRUCTION EXITS SHALL BE MAINTAINED UNTIL DISTURBED PORTIONS OF THE SITE ARE STABILIZED AS DETERMINED BY THE ENGINEER
- 22. CONTRACTOR MUST MAINTAIN ALL EXISTING SERVICES TO THE ABUTTING PROPERTY.
- 23. PRIOR TO STARTING ANY OTHER WORK ON THE SITE, THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES AND SHALL INSTALL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS IDENTIFIED IN FEDERAL, STATE, AND LOCAL APPROVAL DOCUMENTS PERTAINING TO THIS PROJECT.
- 24. THE SITE CONTRACTOR SHALL INSPECT AND MAINTAIN EROSION CONTROL MEASURES ON A WEEKLY BASIS (MINIMUM) OR AS REQUIRED PER THE TOWN OF ARLINGTON CONSERVATION COMMISSION ORDER OF CONDITIONS. THE CONTRACTOR SHALL ADDRESS DEFICIENCIES AND MAINTENANCE ITEMS WITHIN TWENTY-FOUR HOURS OF INSPECTION. CONTRACTOR SHALL PROPERLY DISPOSE OF SEDIMENT SUCH THAT IT DOES NOT ENCUMBER OTHER DRAINAGE STRUCTURES AND PROTECTED AREAS. RECORDS OF THE INSPECTIONS WILL BE PREPARED AND MAINTAINED ON-SITE BY THE CONTRACTOR.



PO Box 9151 Watertown, MA 02471 617.924.1770

XXXX - - TO BE REMOVED

////// - - UTILITIES TO BE ABANDONED IN PLACE




Proposed Self-Storage Facility 34 Dudley St

Arlington, Massachusetts 02476

ARB COMMENTS 4/21/2022

SJH February 9, 2022 **Local Approvals**

Not Approved for Construction





Zoning Summary Chart

Zoning District:	Industrial (I)	
Overlay District:	Inland Wetland	l District
Zoning Regulation Requirements	Required*	Provided
MAXIMUM FRONT YARD SETBACK	10 Feet	10.0 Feet
MINIMUM FRONT YARD SETBACK	10 Feet	10.0 Feet
SIDE YARD SETBACK	10 Feet	10.0 Feet
REAR YARD SETBACK	10 Feet	12.4 Feet
MAXIMUM FLOOR AREA RATIO	3.0	2.72
MAXIMUM BUILDING HEIGHT	65 Feet, 5 Stories	61.5 Feet, 5 Stories **
***	(A 11	

* Zoning regulation requirements as specified in the Town of Arlington Zoning Bylaw, Amended on April 26, 2021, Section 5.6.2

** Building height is calculated as the vertical distance of the highest point of the roof above the average grade of the curb line abutting the property. Parapets excluded per Section 5.3.20. The average grade of the curb line abutting the property is 78.285'. Height of the building is 60.833' from a finished floor elevation of 79.0, therefore the building height to the average grade is 0.715' greater than the actual structure for a calculated zoning building height of 61.548'.

Inland Wetland District Performance Standards

	Existing	Proposed	Improvement
IMPERVIOUS AREA (50' SETBACK)	3790 SF	1253 SF	-2537 SF (66.9%)
IMPERVIOUS SETBACK	25.9 Feet	34.2 Feet	+8.3 Feet

Sign Summary

M.U.T.C.D.	Specif	Specification	
Number	Width	Height	Desc.
R1-1	30"	30"	STOP
R7-8	12"	18"	RESERVED PARKING
R7-8P	12"	6"	VAN ACCESSIBLE
SP-1	12"	18"	RESERVED FOR CARPOOL PARKING
SP-2	12"	18"	NO BOX TRUCKS GREATER THAN 26'

Building Sign Summary

•	ID Niverala au	Sign Type	Sp	pecification	on	Dana	
	ID Number	Sign Type	Width	Height	Area	Desc.	
•	1	Wall Sign	122"	46.5″	39.4 SF	ExtraSpace Storage	
	2	Freestanding Sign	85.5″	39″	23.2 SF	ExtraSpace Storage	
	3	Wall Sign	30"	10"	2.1 SF	OFFICE	

Parking Summary Chart

	Size		Spaces	
Description	Required	Provided	Required	Provided
STANDARD SPACES ¹	8.5 x 18	8.5 x 18	93	18
COMPACT SPACES ²	8 x 16	8 x 18	0	4
ACCESSIBLE SPACES 3	8 x 18	8.5 x 18	-	1
TOTAL SPACES			93	23 ⁶
LOADING BAYS ⁴			3	4
BICYCLE SPACES 5			130	12 ⁶


1. PER SECTION 6.1.5, THE REDEVELOPMENT BOARD CAN GRAND A REDUCTION IN PARKING TO 25% OF THE REQUIRED SPACES. 2. PER SECTION 6.1.11.C.11, THE REDEVELOPMENT BOARD CAN GRANT 20% OF THE PARKING SPACES

TO BE COMPACT.

5. BICYCLE PARKING REQUIRED BASED ON 0.8/1,000 SF LONG TERM AND 0.6/1,000 SF SHORT TERM PARKING. 6 BICYCLE SPACES ARE PROVIDED BY THREE RACKS UNDER THE BUILDING OVERHANG. 4 BICYCLE SPACES ARE PROVIDED AT THE DRIVEWAY ENTRANCE. EMPLOYEE BICYCLE STORAGE WILL

6. WAIVERS REQUESTED FOR REDUCTION IN REQUIRED PARKING SPACES AND REDUCTION IN

	<u> </u>						
STORAGE	92,858 SF	х	1 SPACES	/	1,000 SF	=	93 SPACES
			TOTAL PA	RKIN	IG REQUIRED	=	93 SPACES
		25%	TOTAL PARI	KING	REQUIRED *	=	23 SPACES
	20% MAXIMUM RE	QUIR	ED PARKING	FOR	COMPACT *	=	5 SPACES
•							



Bicycle Parking Requirements:

92,858 SF x 0.60 SPACES / 1,000 SF = 56 SPACES

92,858 SF x 0.80 SPACES / 1,000 SF = 74 SPACES

TOTAL BICYCLE PARKING REQUIRED = 130 SPACES



101 Walnut Street PO Box 9151 Watertown, MA 02471 617.924.1770



34 Dudley St Arlington, Massachusetts 02476

No.	Revision	Date	Appvd
1	ARB COMMENTS	4/21/2022	EKG

Local Approvals	February 9, 2022
Issued for	Date
SJH	EKG
Designed by	Checked by

Not Approved for Construction






^{1.} SIGNS FROM SIGN PACKAGE PREPARED BY ELRO SIGNS FOR EXTRASPACE STORAGE, 34 DUDLEY STREET, ARLINGTON, MA, DATED MARCH 31, 2022. REFER TO SIGN PACKAGE FOR SIGN DETAILS AND



Watertown, MA 02471

617.924.1770




34 Dudley St Arlington, Massachusetts 02476

No.	Revision	Date	Appvd.
1	ARB COMMENTS	4/21/2022	EKG

Local Approvals	February 9, 2022
Issued for	Date
SJH	EKG
Designed by	Checked by

Not Approved for Construction

Grading, Drainage, and Erosion Control Plan



C4.01

Sheet of 4 10


Project Number 52816.00



PO Box 9151

617.924.1770

Watertown, MA 02471



34 Dudley St Arlington, Massachusetts 02476

No.	Revision	Date	Appvd.
1	ARB COMMENTS	4/21/2022	EKG

Not Approved for Construction





Project Number **52816.00**

~ 4½" MIN. DIA. POST

LD_470

1/20

N.T.S.

LD_713

LD_421

6' Single Sided Stockade Fence

2½" MIN ASPHALT BINDER COURSE, MASSDOT M3.11.03

— COMPACTED SUBGRADE

HEAVY DUTY FLEXIBLE PAVEMENT

BASE COURSE FOR PAVEMENT SHOULD BE PLACED IN 12" THICK LOOSE LIFTS AND COMPACTED TO AT LEAST 95 PERCENT OF ITS MAXIMUM DRY DENSITY (MDD) AS DETERMINED BY ASTM D1557 METHOD C (MODIFIED PROTRACTOR).

Source: GeoEngineers, Inc.

Bituminous Concrete Pavement Section

Dumpster Pad w/ Enclosure

RECLAIMED PAVEMENT BORROW (MASSDOT M1.09.0) OR DENSE-GRADED CRUSHED STONE (MASSDOT M2.01.7)

1. ALL FENCING MATERIAL SHALL BE NORTHERN WHITE CEDAR, SAWN TO THE DIMENSIONS SHOWN ON THE DRAWING.

2. ALL FENCE POSTS SHALL BE TREATED WITH PRESERVATIVE PER MANUFACTURER'S RECOMMENDATION ON ALL SIDES FOR A DIMENSION OF 3'-0" FROM BUTT OF POST.

3. POSTS SHALL MAINTAIN A DEPTH OF 2'-10" IN GROUND AND SHALL NOT BE RACKED TO ACCOMMODATE CHANGES IN GRADE.

 LINE OF FENCE TOP AND BOTTOM SHALL BE INSTALLED STRAIGHT AND TRUE.
POSTS AND PICKETS SHALL BE INSTALLED PARALLEL AND PLUMB. RAILS SHALL BE INSTALLED PARALLEL TO GROUND SURFACE AND EACH OTHER.

5. GATE HARDWARE SHALL BE DOUBLE DIP HOT GALVANIZED. THE CONTRACTOR SHALL SUBMIT GATE AND FENCE SHOP DRAWINGS TO THE ENGINEER FOR REVIEW.

> Sign Post - Type 'B' 3/19 LD_702 Source: VHB

EARTH INSITU

HOLE DIAMETER 7/16" —

- TYPICAL SIGN

1. THIS DIMENSION SHALL BE A MINIMUM OF 5' FOR

2. THIS DIMENSION SHALL BE A MAXIMUM OF 8' FOR

(1.75" X 1.75")

— GROUND SURFACE

- ANCHOR SLEEVE (2.25" X 2.25")

- SIGN POST ANCHOR

(2.0" X 2.0")

ACCESSIBLE SIGNAGE.

ACCESSIBLE SIGNAGE

— ROUNDED CONCRETE CAP — CONCRETE FILL — 6" DIA. SCHEDULE 40 STEEL PIPE FILLED WITH CONCRETE COLOR SELECTED BY OWNER/ARCHITECT PAINT PRIME AND FINISH COATS TO BE COMPATIBLE WITH EXTERIOR METAL SURFACES. SURFACE TREATMENT VARIES – 24" DIA. CONCRETE ENCASEMENT — COMPACTED GRAVEL — COMPACTED SUBGRADE


101 Walnut Street PO Box 9151 Watertown, MA 02471 617.924.1770

Bollard N.T.S. Source: VHB

SEE PLAN MOLDED WOODEN CAP - 3" GALVANIZED STEEL POSTS — 1" X 4" CEDAR BOARD — WITH PRESSED DOME CAP (TYP.) — 3" O.D. GALVANIZED STEEL PIPE WITH PRESSED DOME CAP — SCORE LINE (TYP.) 2" X 4" CEDAR BACKING — 2" X 4" CEDAR BACKING RAIL RAIL FASTENED WITH GALVANIZED FASTENED WITH GALVANIZED ADJUSTABLE CLAMP — ADJUSTABLE CLAMP 1" X 6" CEDAR BOARDS SHIPLAP JOINTS — 5000 PSI CEMENT - 1" X 6" SHIP-LAPPED CONCRETE (TYPE II) CEDAR BOARDS — 6" CONCRETE PAD — 5" X 5" STEEL POST — 6" Steel Bollard – DOUBLE GATE COMPACTED GRAVEL COMPACTED SUBGRADE APPROACH APRON **BITUMINOUS OR** CEMENT CONCRETE **SECTION VIEW PLAN VIEW**

1. DUMPSTER PAD DIMENSIONS SHOWN AS MINIMUM. REFER TO PLAN FOR ACTUAL DIMENSION.

Source: VHB






Source: VHB

Painted Pavement Markings - On Site



4000 PSI CEMENT

CONCRETE IF LOCATED IN LANDSCAPED AREA —



LD_700

1. ALL DIMENSIONS TO CENTER OF 4" PAVEMENT STRIPING. 2. ALL SLOPES THROUGHOUT THE ACCESSIBLE PARKING AND AISLE AREAS SHALL NOT EXCEED 1.5%.



TREATMENT VARIES

CONCRETE CURB

— ¾" (MAX.) CHAMFER

— TACK COAT

— BIT. CONCRETE PAVEMENT TOP COURSE (1½" MIN.)

- SAWCUT 12" (MIN.) FROM FACE OF

CURB IF SET IN EXISTING PAVEMENT

- 4000 PSI CEMENT CONCRETE

- 1½" BY 2½" DOWEL SOCKETS

OF ALL CURB SECTIONS TO

RECEIVE ½" DIA. DOWEL

SHALL BE FURNISHED AT ENDS

- COMPACTED GRAVEL

(1½" MAX. STONE SIZE)

- COMPACTED SUBGRADE

STEEL REINFORCED PRECAST

Facility 34 Dudley St Arlington, Massachusetts 02476

1	ARB COMMENTS	4/21/2022	EKG

Proposed Self-Storage

Designed by MEA	Checked by EKG		
Issued for	Date		
Local Approvals	February 9, 2022		






LIGHT POLE & ANCHORING PROVIDE BASE COVER SYSTEM BY MFG. AS FURNISHED BY POLE MFG. — - LIGHT POLES BASES IN PARKING LOT TO - REINFORCEMENT – FINISH GRADE (MATERIALS VARY) TYP. COVER - 5,000 PSI CONCRETE, TYPE II CEMENT CONDUIT AND GROUND ROD CONNECT TO INSIDE METAL POLE SEE ELECTRICAL PLAN FOR SIZE BOLT LAYOUT COMPACTED OR UNDISTURBED & MOUNTING PROCEDURE AS PER MFG. SPECS — ON REBAR SECTION NOTES DETAIL PROVIDED FOR GENERAL INFORMATION ONLY. CONTRACTOR TO PROVIDE STAMPED FINAL DESIGN OF LIGHT POLE FOUNDATION BASED ON RECOMMENDATIONS FROM THE GEOTECHNICAL ENGINEER.


LD_310A


Light Pole Foundation Detail (Up to 15' Pole)



Source: VHB

TYPICAL SPACING






PRODUCT.				
oncrete Sidewalk		3/20	Precast Concrete Curb (PCC)	
T.S.	Source: VHB	LD_420	N.T.S.	Source: \


LD_404

Project Number 52816.00




Source: VHB

LD_260



Typical Driveway with Sidewalk and Curved Transition Curb

Concrete Thrust Block







SECTION A-A


CRUSHED STONE

(2" STONE SIZE)

COMPACTED SUBGRADE —









OUTLET STRUCTURE CHART

100 75.9 6.5" x 4" 71.7 5.5" x 6" 73.4

SSIS 1


GRADE —

WATER-TIGHT JOINT -

N.T.S.

SEE NOTE 5. —

Outlet Control Structure with Weir (OCS)



1. AREA DRAINS SHALL BE NYLOPLAST 12" DIAMETER DRAIN BASIN, OR APPROVED EQUAL.

2. GRATES SHALL BE NYLOPLAST 12" PEDESTRIAN MODEL 1299CGP OR 12" DOME GRATE MODEL 1299CGD

ACCESS

8" ACCESS 8"

GRADE —

SHELF TO BE SEWER

BRICK LAID FLAT AT A

COMPACTED GRAVEL —

COMPACTED SUBGRADE —

Sanitary Sewer Manhole (SMH)

SLOPE OF 1"/FOOT —

N.T.S.

PIPE PER PLANS

(REFER TO UTILITY TRENCH DETAIL) —

FLOW

COMPACTED

Area Drain (AD) Type 1

N.T.S.

SUBGRADE —

ALTERNATE TOP SLAB

(STEEL REINFORCED FOR HS-20 LOADING)

STEPS, SEE

NOTE2.

48" DIA. MANHOLE (MIN.)

STRUCTURES SHALL BE PRECAST

DEPTH OF THE STRUCTURE.

4. JOINT SEALANT BETWEEN PRECAST

PROOFING MATERIAL.

- SEE NOTE 3

- SEE NOTE 4.

- ARCH INVERT TO BE CONSTRUCTED

→ / ADA-COMPLIANT FLUSH GRATE

— HARDSCAPE

WITH SEWER BRICK LAID AS

STRETCHERS AND ON EDGE

- BRICK CHIP AND

CONCRETE FILL

12" MIN

MORTAR OR CEMENT

- FLEXIBLE WATERTIGHT GASKET OR SLEEVE

CONCRETE, DESIGNED FOR HS-20

COPOLYMER MANHOLE STEPS SHALL BE

INSTALLED AT 12" O.C. FOR THE FULL

EXTERIOR SURFACES SHALL BE GIVEN

TWO COATS OF BITUMINOUS WATER-

SECTIONS SHALL BE PREFORMED BUTYL

5. STANDARD SEWER MANHOLE FRAME

AND COVER SHALL BE SET IN FULL

MORTAR BED. ADJUST TO GRADE WITH SEWER BRICK AND MORTAR (2 BRICK

COURSES TYPICALLY, 5 BRICK COURSES

LD_200

CONCRETE COLLAR

12/19


LD_193

COMPACTED GRAVEL


3. FOR HDPE, PVC, AND DI PIPE, PROVIDE FLEXIBLE BOOT CONNECTION INSTALLED PER MANUFACTURER'S RECOMMENDATIONS. FOR RCP, PROVIDE OPENINGS FOR PIPES WITH 2" MAX. CLEARANCE TO OUTSIDE OF PIPE AND MORTAR CONNECTIONS. 4. JOINT SEALANT BETWEEN PRECAST SECTIONS SHALL BE PREFORMED BUTYL RUBBER.

5. DRAIN MANHOLE FRAME AND COVER SHALL BE SET IN FULL MORTAR BED. ADJUST TO GRADE WITH CLAY BRICK AND MORTAR (2 BRICK COURSES TYPICALLY, 5 BRICK


Utility Trench 3/20 N.T.S.







Drain Manhole (DMH) Source: VHB



1. WHERE UTILITY TRENCHES ARE CONSTRUCTED THROUGH DETENTION BASIN BERMS OR OTHER SUCH SPECIAL SECTIONS, PLACE TRENCH BACKFILL WITH MATERIALS SIMILAR TO THE SPECIAL SECTION REQUIREMENTS.

2. USE METALLIC TRACING/WARNING TAPE OVER ALL PIPES. 3. COMPACTED GRANULAR FILL MAY CONSIST OF GRAVEL, CRUSHED STONE, SAND, OR OTHER MATERIAL AS APPROVED BY ENGINEER.

Proposed Self-Storage Facility

101 Walnut Street

Watertown, MA 02471


PO Box 9151

617.924.1770

34 Dudley St Arlington, Massachusetts 02476

No.	Revision	Date	Appvd.
1	ARB COMMENTS	4/21/2022	EKG
Design	MEA	Checked by	(G
Issued	for	Date	
	cal Approvals	February 9,	2022





Project Number 52816.00

PRECAST CONCRETE WEIR WITH CONTROL ORIFICE(S) SEE NOTE 4 -INVERT ORIFICE B

 COMPACTED GRAVEL SECTION A-A — COMPACTED SUBGRADE

Source: VHB


LD_162A


Source: VHB LD_300

11/19

- 1. BEGIN AT THE TOP OF BLANKET INSTALLATION AREA BY ANCHORING BLANKET IN A 6" DEEP TRENCH BACKFILL AND COMPACT TRENCH AFTER STAPLING.
- 2. ROLL THE BLANKET DOWN THE SWALE IN THE DIRECTION OF THE WATER FLOW.
- 3. THE EDGES OF BLANKETS MUST BE STAPLED WITH APPROX. 4 INCH OVERLAP WHERE 2 OR MORE STRIP WIDTHS ARE REQUIRED.
- 4. WHEN BLANKETS MUST BE SPLICED DOWN THE SWALE, PLACE UPPER BLANKET END OVER LOWER END WITH 6 INCH (MIN.) OVERLAP AND STAPLE BOTH TOGETHER.
- 5. METHOD OF INSTALLATION SHALL BE AS PER MANUFACTURER'S RECOMMENDATIONS.
- 6. EROSION CONTROL BLANKETS SHALL BE USED IN ALL AREAS WHERE SLOPES EXCEED 3:1.

Erosion Control Blanket Slope Installation 10/20 LD_680





101 Walnut Street

Watertown, MA 02471


PO Box 9151


617.924.1770

- 1. SILTSOCK SHALL BE FILTREXX SILTSOXX, OR APPROVED EQUAL. 2. SILTSOCKS SHALL OVERLAP A MINIMUM OF 12 INCHES.
- 3. SILTSOCK SHALL BE INSPECTED PERIODICALLY AND AFTER ALL STORM
- EVENTS, AND REPAIR OR REPLACEMENT SHALL BE PERFORMED PROMPTLY 4. UPON SITE STABILIZATION, COMPOST MATERIAL SHALL BE DISPERSED ON
- SITE, AS DETERMINED BY THE ENGINEER.

5. IF NON BIODEGRADABLE NETTING IS USED THE NETTING SHALL BE COLLECTED AND DISPOSED OF OFFSITE.

Siltsock - Erosion Control Barrier 10/20 LD_658





Stormtech Inspection Port		Stormtech En	d Cap Insertion
N.T.S.	Source: Stormtech	N.T.S.	Source: Stori

NOTE: PART NUMBERS WILL VARY BASED ON INLET PIPE MATERIALS. CONTACT STORMTECH FOR MORE INFORMATION.

Stormtech Inserta-Tee Side Inlet

PLACE ADSPLUS WOVEN GEOTEXTILE
(CENTERED ON INSERTA-TEE INLET) OVER
BEDDING STONE FOR SCOUR PROTECTION
AT SIDE INLET CONNECTIONS. GEOTEXTILE
MUST EXTEND 6" (150 mm) PAST CHAMBER
FOOT

ACCEPTABLE FILL MATERIALS: STORMTECH MC-4500 CHAMBER SYSTEMS

SIDE VIEW

MC-4500 12" (300 mm) 8" (200 mm)

INSERTA TEE FITTINGS AVAILABLE FOR SDR 26, SDR 35, SCH 40 IPS
GASKETED & SOLVENT WELD, N-12, HP STORM, C-900 OR DUCTILE IRON

MAX DIAMETER OF HEIGHT FROM BASE OF

MATERIAL LOCATION		DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT	
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.	
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE (B' LAYER) TO 24" (600 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145¹ A-1, A-2-4, A-3 OR AASHTO M43¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 24" (600 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 12" (300 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS.	
В	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	NO COMPACTION REQUIRED.	
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. ^{2,3}	


PLEASE NOTE:

1. THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".

2. STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 9" (230 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.


3. WHERE INFILITATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.

4. ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.




- 1. CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" CHAMBER CLASSIFICATION 60x101 2. MC-4500 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". 3. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION
- FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS. 4. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
 5. REQUIREMENTS FOR HANDLING AND INSTALLATION:
- TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
- TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 3". TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 500 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.


Subsurface Detention/Infiltration System (StormTech MC-4500)




- 1. INSTALL SILTSACK IN ALL CATCH BASINS WHERE INDICATED ON THE PLAN BEFORE COMMENCING WORK OR IN PAVED AREAS AFTER BINDER COURSE IS PLACED AND HAY BALES HAVE BEEN REMOVED.
- 2. GRATE TO BE PLACED OVER SILTSACK.
- 3. SILTSACK SHALL BE INSPECTED PERIODICALLY AND AFTER ALL STORM EVENTS AND CLEANING OR REPLACEMENT SHALL BE PERFORMED PROMPTLY AS NEEDED. MAINTAIN UNTIL UPSTREAM AREAS HAVE BEEN PERMANENTLY STABILIZED

Siltsack Sediment Trap







CROSS-SECTION

PROVIDED AS NEEDED.

- 1. EXIT WIDTH SHALL BE A TWENTY-FIVE (25) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS
- 2. THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH SHALL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY. BERM SHALL BE PERMITTED. PERIODIC INSPECTION AND MAINTENANCE SHALL BE
- 3. STABILIZED CONSTRUCTION EXIT SHALL BE REMOVED PRIOR TO FINAL FINISH MATERIALS BEING INSTALLED.

Stabilized Cor	struction Exit	1/16
N.T.S.	Source: VHB	LD_682


Proposed Self-Storage Facility

34 Dudley St Arlington, Massachusetts 02476

1	ARB COMMENTS	4/21/2022	EKG

Designed by MEA	Checked by EKG
Issued for	Date
Local Approvals	February 9, 2022

Not Approved for Construction





Project Number

StormTech MC-4500 Isolator Row Profile

COVER PIPE CONNECTION TO END CAP WITH ADS -GEOSYNTHETICS 601T NON-WOVEN GEOTEXTILE

SUMP DEPTH TBD BY SITE DESIGN ENGINEER (24" [600 mm] MIN RECOMMENDED)

Source: StormTech

C ONE LAYER OF ADSPLUS175 WOVEN GEOTEXTILE BETWEEN FOUNDATION STONE AND CHAMBERS 10.3' (3.1 m) MIN WIDE CONTINUOUS FABRIC WITHOUT SEAMS

INSPECTION & MAINTENANCE

STEP 1) INSPECT ISOLATOR ROW PLUS FOR SEDIMENT
A. INSPECTION PORTS (IF PRESENT)
A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN
A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
A.3. USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG
A.4. LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL)

STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS

A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45" (1.1 m) OR MORE IS PREFERRED

B. APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN
C. VACUUM STRUCTURE SUMP AS REQUIRED

1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.

2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.

STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

A.5. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.

B. ALL ISOLATOR PLUS ROWS

B.1. REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS

B.2. USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE

1. MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY

1. FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE

B.3. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.

N.T.S.

N.T.S.

Source: VHB

Planting Notes

PLANT SCHEDULE

- 1. ALL PROPOSED PLANTING LOCATIONS SHALL BE STAKED AS SHOWN ON THE PLANS FOR FIELD REVIEW AND APPROVAL BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- 2. CONTRACTOR SHALL VERIFY LOCATIONS OF ALL BELOW GRADE AND ABOVE GROUND UTILITIES AND NOTIFY OWNERS REPRESENTATIVE OF CONFLICTS.
- 3. NO PLANT MATERIALS SHALL BE INSTALLED UNTIL ALL GRADING AND CONSTRUCTION HAS BEEN COMPLETED IN THE IMMEDIATE AREA. CONTRACTOR SHALL NOTIFY OWNER'S REPRESENTATIVE OF ANY CONFLICT.
- 4. A 3-INCH DEEP MULCH PER SPECIFICATION SHALL BE INSTALLED UNDER ALL TREES AND SHRUBS, AND IN ALL PLANTING BEDS, UNLESS OTHERWISE INDICATED ON THE PLANS, OR AS DIRECTED BY OWNER'S REPRESENTATIVE.
- 5. ALL TREES SHALL BE BALLED AND BURLAPPED, UNLESS OTHERWISE NOTED IN THE DRAWINGS OR SPECIFICATION, OR APPROVED BY THE OWNER'S REPRESENTATIVE.
- 6. FINAL QUANTITY FOR EACH PLANT TYPE SHALL BE AS GRAPHICALLY SHOWN ON THE PLAN. THIS NUMBER SHALL TAKE PRECEDENCE IN CASE OF ANY DISCREPANCY BETWEEN QUANTITIES SHOWN ON THE PLANT LIST AND ON THE PLAN. THE CONTRACTOR SHALL REPORT ANY DISCREPANCIES BETWEEN THE NUMBER OF PLANTS SHOWN ON THE PLANT LIST AND PLANT LABELS PRIOR TO BIDDING.

- ANY PROPOSED PLANT SUBSTITUTIONS MUST BE REVIEWED BY LANDSCAPE ARCHITECT AND APPROVED IN WRITING BY THE OWNER'S REPRESENTATIVE.
- 8. ALL PLANT MATERIALS INSTALLED SHALL MEET THE SPECIFICATIONS OF THE "AMERICAN STANDARDS FOR NURSERY STOCK" BY THE AMERICAN ASSOCIATION OF NURSERYMEN AND CONTRACT DOCUMENTS.
- 9. ALL PLANT MATERIALS SHALL BE GUARANTEED FOR ONE YEAR FOLLOWING DATE OF FINAL ACCEPTANCE.
- 10. AREAS DESIGNATED "LOAM & SEED" SHALL RECEIVE MINIMUM 6" OF LOAM AND SPECIFIED SEED MIX. LAWNS OVER 2:1 SLOPE SHALL BE PROTECTED WITH EROSION CONTROL FABRIC.
- 11. ALL DISTURBED AREAS NOT OTHERWISE NOTED ON CONTRACT DOCUMENTS SHALL BE LOAM AND SEEDED OR MULCHED AS DIRECTED BY OWNER'S REPRESENTATIVE.
- 12. THIS PLAN IS INTENDED FOR PLANTING PURPOSES. REFER TO SITE / CIVIL DRAWINGS FOR ALL OTHER SITE CONSTRUCTION INFORMATION.

Plant Maintenance Notes

1. CONTRACTOR SHALL PROVIDE COMPLETE MAINTENANCE OF THE LAWNS AND PLANTINGS. NO IRRIGATION IS PROPOSED FOR THIS SITE. THE CONTRACTOR SHALL SUPPLY SUPPLEMENTAL WATERING FOR NEW LAWNS AND PLANTINGS DURING THE ONE YEAR PLANT GUARANTEE PERIOD.

2. CONTRACTOR SHALL PROVIDE ALL MATERIALS, LABOR, AND EQUIPMENT FOR THE COMPLETE LANDSCAPE MAINTENANCE WORK. WATER SHALL BE PROVIDED BY THE CONTRACTOR.

3. WATERING SHALL BE REQUIRED DURING THE GROWING SEASON, WHEN NATURAL RAINFALL IS BELOW ONE INCH PER WEEK.

4. WATER SHALL BE APPLIED IN SUFFICIENT QUANTITY TO THOROUGHLY SATURATE THE SOIL IN THE ROOT ZONE OF EACH PLANT.


5. CONTRACTOR SHALL REPLACE DEAD OR DYING PLANTS AT THE END OF THE ONE YEAR GUARANTEE PERIOD. CONTRACTOR SHALL TURN OVER MAINTENANCE TO THE FACILITY MAINTENANCE STAFF AT THAT TIME.

101 Walnut Street PO Box 9151 Watertown, MA 02471 617.924.1770

DECIDUOUS TREES AR CB	<u>QTY</u> 5 7	BOTANICAL NAME Acer rubrum Carpinus betulus `Fastigiata`	COMMON NAME Red Maple Pyramidal European Hornbean	SIZE 2 1/2 - 3" CAL. 2 1/2 - 3" CAL.	
EVERGREEN TREES JV TO	QTY 21 12	BOTANICAL NAME Juniperus virginiana Thuja occidentalis `Nigra`	COMMON NAME Eastern Redcedar Dark American Arborvitae	<u>SIZE</u> 6 - 7` HT. 5 - 6` HT.	
SHRUBS IG JB LA RGL	QTY 30 61 16 6	BOTANICAL NAME Ilex glabra Juniperus horizontalis `Bar Harbor` Leucothoe axillaris Rhus aromatica `Gro-Low`	COMMON NAME Inkberry Bar Harbor Creeping Juniper Coastal Leucothoe Gro-Low Fragrant Sumac	SIZE 2 - 3` HT. 18 - 24" SPD 18 - 24" SPD 18 - 24" SPD	
GROUNDCOVER VM	QTY 3	BOTANICAL NAME Vinca minor	COMMON NAME Periwinkle	SIZE 1 GAL.	
ORNAMENTAL GRASSES SSB SH	<u>QTY</u> 78 58	BOTANICAL NAME Schizachyrium scoparium Sporobolus heterolepis	COMMON NAME Little Bluestem Grass Prairie Dropseed	SIZE 2 GAL. 2 GAL.	SPACI 24" o. 24" o.

Seed Mixtures:

- 1. AREAS INDICATED AS "BIORETENTION BASIN" ARE TO BE SEEDED WITH NEW ENGLAND EROSION CONTROL / RESTORATION MIX FOR DETENTION PONDS AND MOIST AREAS, AS MANUFACTURED BY NEW ENGLAND WETLAND PLANTS, INC. AMHERST, MA (413) 548-8000, www.NEWP.com,OR AN APPROVED EQUAL. APPLY IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
- 2. AREAS INDICATED AS "EROSION CONTROL SEED MIX" ARE TO BE SEEDED WITH NEW ENGLAND CONSERVATION EROSION CONTROL/RESTORATION MIX FOR DRY SITES, AS MANUFACTURED BY NEW ENGLAND WETLAND PLANTS, INC. AMHERST, MA (413) 548-8000, www.NEWP.com,OR AN APPROVED EQUAL. APPLY IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.




34 Dudley St Arlington, Massachusetts 02476

1 ARB COMMENTS 4/21/2022	
	EKG

Designed by SJH	Checked by EKG
Issued for	Date
Local Approvals	February 9, 2022


Not Approved for Construction










101 Walnut Street PO Box 9151 Watertown, MA 02471 617.924.1770









NOTES

LD_605

1. LOOSEN ROOTS AT THE OUTER EDGE OF ROOTBALL OF CONTAINER GROWN SHRUBS.

Shrub Bed Planting		1/16
N.T.S.	Source: VHB	LD_601

Stone Mulch 11/15 N.T.S. LD_{-} Source: VHB

1. EDGE CONDITIONS VARIES. WHERE

STONE MUCH DOES NOT ABUT CURB

OR BUILDING FACE PROVIDE 12" LONG

NOTES


STEEL EDGING

- 3/4" WASHED STONE


- MIRAFI 140N FILTER FABRIC

- COMPACTED SUBGRADE

Perennial and Ornamental Grass Planting N.T.S. LD_618 Source: VHB



Source: VHB




Tree Planting (For Trees Under 4" Caliper) 9/21 N.T.S. LD_602 Source: VHB




Arlington, Massachusetts 02476

SJH February 9, 2022 **Local Approvals**


Not Approved for Construction





52816.00

Project Number



General Notes


- 1) THE PROPERTY LINES SHOWN ON THIS PLAN ARE BASED UPON AN ACTUAL FIELD SURVEY CONDUCTED BY VHB, INC. IN OCTOBER, 2021 AND FROM DEEDS AND PLANS OF RECORD.
- 2) THE EXISTING CONDITIONS SHOWN ON THIS PLAN ARE BASED UPON AN ACTUAL ON-THE-GROUND INSTRUMENT SURVEY PERFORMED BY VHB, INC. IN OCTOBER, 2021.
- 3) THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED ON FIELD OBSERVATIONS AND INFORMATION OF RECORD. THEY ARE NOT WARRANTED TO BE EXACTLY LOCATED NOR IS IT WARRANTED THAT ALL UNDERGROUND UTILITIES OR OTHER STRUCTURES ARE SHOWN ON THIS PLAN.
- 4) HORIZONTAL DATUM IS BASED ON MASS. GRID SYSTEM, NAD 1983. ELEVATIONS SHOWN ON THIS PLAN REFER TO NAVD OF 1988.
- 5) THE WETLANDS SHOWN ON THIS PLAN WERE FLAGGED BY VHB ENVIRONMENTAL DEPARTMENT AND FIELD SURVEYED BY VHB IN OCTOBER, 2021.
- 6) THE TREE SYMBOL OUTLINE SHOWN ON THIS PLAN DOES NOT REPRESENT THE ACTUAL TREE CANOPY.
- 7) THE LOT LIES ENTIRELY WITHIN ZONE X (UNSHADED) (AREAS TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN) AS SHOWN ON THE FLOOD INSURANCE RATE MAP FOR MIDDLESEX COUNTY, MASSACHUSETTS, MAP NUMBER 25017C0416E, EFFECTIVE DATE JUNE 4, 2010.

Zoning

THE LOT LIES ENTIRELY WITHIN THE INDUSTRIAL DISTRICT (I) AS SHOWN ON GIS MAPPING FOR THE TOWN OF ARLINGTON MASSACHUSETTS" AND THE INLAND WETLAND OVERLAY DISTRICT. DIMENSIONAL REQUIREMENTS FOR A (I) AT THE TIME OF THIS SURVEY ARE:

	REQUIRED	EXISTING
MINIMUM LOT AREA	N/A	34,104 S.F
MINIMUM FRONTAGE	N/A	129.01 FEET
MINIMUM FRONT YARD SETBACK	10 FEET	57.0 FEET
MINIMUM SIDE YARD SETBACK	10 FEET	0.0 FEET
MINIMUM REAR YARD SETBACK	10 FEET	6.1 FEET
MAXIMUM BUILDING HEIGHT	65*/39 FEET	23.8 FEET

*SUBJECT TO AMENITY REQUIREMENTS IN SECTION 5.6.2 D(7)





101 Walnut Street PO Box 9151 Watertown, MA 02471 617.924.1770

Legend DRAIN MANHOLE ■ CATCH BASIN S SEWER MANHOLE © ELECTRIC MANHOLE TELEPHONE MANHOLE MANHOLE HH□ HAND HOLE WATER GATE FIRE HYDRANT GAS GATE ■ BOLLARD w/LIGHT - STREET SIGN □ LIGHT POLE -O- UTILITY POLE ○— GUY POLE GUY WIRE MONITORING WELL FLOOD LIGHT WELL WELL <u>₩</u> MARSH F.F.E.=45.27' FINISHED FLOOR ELEVATION

CNO COULD NOT OPEN
NPV NO PIPES VISIBLE
DYL DOUBLE YELLOW LINE
DWL DASHED WHITE LINE
SYL SINGLE YELLOW LINE

LSA LANDSCAPED AREA
EDGE OF PAVEMENT
CONCRETE CURB
VGC
VGC
VERTICAL GRANITE CURB
SGE
SLOPED GRANITE EDGE
BITUMINOUS BERM
BITUMINOUS CURB
GUARD RAIL
OOOOO CHAIN LINK FENCE

DRAINAGE LINE
SEWER LINE
OVERHEAD WIRE
UNDERGROUND ELECTRIC
TELEPHONE LINE
GAS LINE
WATER LINE
STONE WALL

TREE LINE

100'BZ 100-FT BUFFER ZONE

100-FT RIVER FRONT AREA

200'RA 200-FT RIVER FRONT AREA


LIMIT MEAN ANNUAL HIGH WATER

LIMIT OF BANK

WF1-100 VEGETATED WETLAND BOUNDARY

Self-Storage


34 Dudley Street Arlington, Massachusetts








Project Number **52816.00**





10' SET BACK

PROPERTY LINE

NORTH

1st. FLOOR GROSS
9,067 sq.ft. - Storage
907 sq.ft. - Office
9,974 sq. ft TOTAL

BUILDING GROSS
91,754 sq.ft. - Storage
907 sq.ft. - Office
92,858 sq. ft TOTAL

SELF STORAGE

ARLINGTON, MASSACHUSETTS
Project No. 21-033



Local Approvals Submission
April 21, 2022
REVISIONS


No. Description Date

1st. FLOOR PLAN

A-101

Copyright 2021 Michael Parker Studios PLLC





2nd. FLOOR GROSS 20,721 sq. ft TOTAL EACH





ARLINGTON, MASSACHUSETTS Project No. 21-033



Local Approvals Submission

April 21, 2022					
	REVISIONS				
No.	Description				
		-			
-					
	+				
-					


2nd. FLOOR PLAN

Copyright 2021 Michael Parker Studios PLLC



3 A201 10x10 В
 5x5
 5x5
 5x5
 5x5
 5x5
 5x5
 ELEV ELEV. 10x15 10x15 10x15 D ____ 10x10 10x10 10x10 E ---5x10 F----__10x10_____10x10_____10x10__ 5x10 5x10 G 10x10 10x10 10x10 10x10 10x10 5x10 5x7.5 | 5x7.5 | 5x7.5 | 5x7.5 195 sf. UNIT 5x10 H — 5x10 133 sf. UNIT 38 sf. UNIT 5x10 10x10 10x10 5x10 J K _____

3rd. FLOOR GROSS 20,721 sq. ft TOTAL





ARLINGTON, MASSACHUSETTS



Local Approvals Submission
April 21, 2022

April 21, 2022					
REVISIONS					
No.	Description	Date			

3rd. FLOOR PLAN

A-103

Copyright 2021 Michael Parker Studios PLLC



3 A201 10x10 В 5x5 5x5 5x5 5x5 5x5 5x5 ELEV ELEV. 10x15 10x15 10x15 10x15 10x15 10x15 D ____ 10x10 10x10 10x10 E---5x10 F----__10x10_____10x10_____10x10__ 5x10 5x10 G ___10x10____10x10_ 5x10 5x7.5 | 5x7.5 | 5x7.5 | 5x7.5 195 sf. UNIT 5x10 H — 5x10 133 sf. UNIT 38 sf. UNIT 5x10 10x10 10x10 5x10 J K _____


4th. FLOOR GROSS 20,721 sq. ft TOTAL EACH





SELF STORAGE

ARLINGTON, MASSACHUSETTS
Project No. 21-033




Local Approvals Submission
April 21, 2022
REVISIONS

No. Description Date


4th. FLOOR PLAN

A-104
Copyright 2021 Michael Parker Studios PLLC






5th. FLOOR GROSS 20,721 sq. ft TOTAL EACH





ARLINGTON, MASSACHUSETTS

Project No. 21-033





Local Approvals Submission April 21, 2022

REVISIONS ____

5th. FLOOR PLAN

A-105











SELF STORAGE

ARLINGTON, MASSACHUSETTS Project No. 21-033





Local Approvals Submission April 21, 2022


	REVISIONS	
No.	Description	Dat

ROOF PLAN

Copyright 2021 Michael Parker Studios PLLC









SELF STORAGE

ARLINGTON, MASSACHUSETTS Project No. 21-033



Local Approvals Submission April 21, 2022


REVISIONS ____ -____ ____ ____ ____

EXTERIOR ELEVATIONS

Copyright 2021 Michael Parker Studios PLLC


2 ELEVATION - NORTH

scale: 1/8"=1'-0"





2 ELEVATION - SOUTH scale: 1/8"=1'-0"





SELF STORAGE

ARLINGTON, MASSACHUSETTS Project No. 21-033



Local Approvals Submission		
April 21, 2022		
REVISIONS		
No.	Description	Date

EXTERIOR ELEVATIONS

Copyright 2021 Michael Parker Studios PLLC