



TOWN OF ARLINGTON  
 Department of Public Works  
 51 Grove Street  
 Arlington, Massachusetts 02476  
 Office (781) 316-3320 Fax (781) 316-3281

Engineering Division

June 10, 2024

**IFB #24-55: Lead Service Line Inspection & Replacement – Various Locations**

**Addendum No. 1**

The attention of Bidders submitting bids for the above-referenced project is called to the following Addendum to the Invitation for Bids. The items set forth herein, whether of omission, addition, substitution, or clarification, shall be included in and form a part of the proposal submitted and shall become part of the Contract.

**1. Bidder Question Responses:**

- **Question: Is this a MassDOT prequalification project? If so, what is the class of work? Please verify the project estimate.**
  - **Answer:** No, this is not a MassDOT prequalification project. The project estimate represents the Town’s best approximation of the work to be completed based on currently available information. It is anticipated that the scope of work at some locations will be Test Pits only.
- **Question: Can the Town provide a list of the proposed water services they intend to do on the project?**
  - **Answer:** A list of projected locations to be investigated under this project is listed below, as well as what available records indicate the public-side and private-side service materials may currently be. As noted in the technical specifications, Test Pits will be required at each location to confirm the scope of replacement work required, if any. Based on previous lead service replacement efforts in Town, it is anticipated that approximately half of the locations noted below will already have “full” length copper services. Additionally, the Town is actively trying to classify service materials for properties with suspected lead service lines. As such, it is possible that some locations may be removed from this list by the time the contract is executed.

Location	Public Side Service Material	Private Side Service Material	Sidewalk Material
7 Aberdeen Road	Lead	Copper	No sidewalk
15 Aberdeen Road	Lead	Lead	Asphalt
35 Aberdeen Road	Lead	Copper	Concrete

Location	Public Side Service Material	Private Side Service Material	Sidewalk Material
272 Appleton Street	Lead	Lead	Concrete
4 Argyle Road	Lead	Copper	Concrete
19 Foster Street	Lead	Lead	Concrete
31 Governor Road	Lead	Copper	No sidewalk
21 Highland Avenue	Copper	Lead	Concrete
55 Hillside Avenue	Lead	Lead	Concrete
26 Kilsythe Road	Lead	Copper	Concrete
30 Kilsythe Road	Lead	Iron	Concrete
1288 Massachusetts Avenue	Lead	Copper	Asphalt
1294 Massachusetts Avenue	Lead	Lead	Asphalt
416 Mystic Street	Lead	Copper	No sidewalk
418 Mystic Street	Lead	Iron	No sidewalk
56 Palmer Street	Lead	Lead	Concrete
313 Park Avenue	Lead	Iron	Concrete
26 Paul Revere Road	Lead	Copper	Asphalt
195 Pleasant Street	Copper	Lead	Concrete
199 Pleasant Street	Lead	Lead	Concrete
201 Pleasant Street	Lead	Iron	Concrete
89 Oakland Avenue	Lead	Lead	Concrete
74 Rhinecliff Street	Iron	Iron	Concrete
180 Scituate Street	Lead	Copper	No sidewalk
75 Westminster Avenue	Lead	Copper	Concrete

All other terms and conditions of the bid documents remain unchanged.

**ADDENDUM MUST BE ACKNOWLEDGED ON THE BID FORM. FAILURE TO ACKNOWLEDGE ANY OR ALL ADDENDA COULD RESULT IN REJECTION OF YOUR BID AS NON-RESPONSIVE.**

James Feeney  
Town Manager